DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW SQUARE STEEL POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
THETFORD US 5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W13-1	18	18		20 MPH PLAQUE			1				X															
SB	5.265	F	M3-3	24	12		SOUTH						1		X														
		F	M1-4	24	24		US 5						1																
SB	5.225	G	VR-017	24	30		LLL 24,000 LBS			1				X													CIDER MILL RD TH-16			
SB	5.215	H	R1-1	30	30		STOP			1				X													CIDER MILL RD TH-16 - ISLAND			
SB	5.205	H	R1-1	30	30		STOP			1				X													CIDER MILL RD TH-16			
SB	5.184	F	R2-1	24	30		SPEED LIMIT 40			1				X															
SB	5.032	F	W1-10L	30	30		LEFT CURVE			1				X															
SB	5.032	F	W16-8A	18	8		LATHAM RD			1				X															
SB	4.963	F	W1-6	48	24		LEFT <=== LARGE ARROW			1				X															
SB	4.962	E	W1-6	48	24		RIGHT ===> LARGE ARROW			1				X															
SB	4.901	G	VR-017	24	30		LLL 24,000 LBS			1				X													LATHAM RD TH-5			
SB	4.901	H	R1-1	30	30		STOP			1				X													LATHAM RD TH-5			
SB	4.763	F	R2-1	24	30		SPEED LIMIT 50			1				X															
SB	3.750	F	D9-1	24	24		PHONE						1		X														
							SHEET TOTALS	0.00 SF	0.00 SF	12 EA	0 EA	0 EA	3 EA	0 EA	0 EA	0 EA		0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	245.6	0.0	26	3	3	61	0	0	29		435.0		4		364.8									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: NORWICH - FAIRLEE
PROJECT NUMBER: STPG SIGN (34)

FILE NAME: 10C334
PROJECT MANAGER: A.GAMBLE
DESIGNED BY: D.CROSSLEY
THETFORD US 5 SOUTHBOUND 2

PLOT DATE: 5/2/2011
DRAWN BY: D.CROSSLEY
CHECKED: QAU