DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW SQUARE STEEL POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
THETFORD US 5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M3-2	24	12								1															
		F	M1-5A	30	24								1															
		F	M6-1	21	15								1															
		F	VD1-1A	72	12			6.00												2	182.4					THINNING AND TRIMMING		4	
		F	VD1-1A	72	12		Pompanoosuc 5	6.00																				4	
		F	VD1-1	72	12		Norwich 10	6.00																				4	
		F	M3-2	24	12		Lyme N.H.	2.00																		GREEN ON WHITE	X		
		F	M1-5A	30	24		EAST	5.00																					E-136B
		F	M6-1	21	15		VERMONT 113	2.19																		GREEN ON WHITE	X		
SB	2.987	F	R8-3	24	24		NO PARKING	4.00		~~1~~			1	X													X		
			M4-6	24	12		END						1													OLD SIGN WAS REPLACED			
SB	2.950	F	W10-3L	36	36		SIDE ROAD WARNING WITH TRACKS			1				X															
	2.945	F	VR-020	24	30		NO PARKING ON TRAVELED LANES						1		X														
			R2-1	24	30		SPEED LIMIT 30	5.00								1		X									X		
			R8-3	24	24		R	4.00																			X		
							SHEET TOTALS	~~36.19~~ 40.19	0.00	~~2~~ 1	0	0	~~5~~ 6	0	0	1		15		2	182.4	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	245.6	0.0	26	3	3	61	0	0	29		435.0		4		364.8							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: NORWICH - FAIRLEE
PROJECT NUMBER: STPG SIGN (34)

FILE NAME 10C334
PROJECT MANAGER A.GAMBLE
DESIGNED BY: D.CROSSLEY
THETFORD US 5 SOUTHBOUND 7

PLOT DATE: 5/2/2011
DRAWN BY: D.CROSSLEY
CHECKED QAU
SHEET 36 OF 65