DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW SQUARE STEEL POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET NUMBER	SIGN DETAIL LOCATION STANDARD SHEET NUMBER
FAIRLEE US 5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	3.520	A	VR-654	24	24		NO DWI						1		X													
		A	VR-655	24	18		STRICTLY ENFORCED						1															
NB	3.570	A	R2-1	24	30								1		X													
			W16-18P	24	12	FY	STATE LAW	2.00								1		X									5	
			R2-1	24	30		SPEED LIMIT 50	5.00																			X	
			R2-5P	24	18		UNLESS OTHERWISE POSTED	3.00																			X	
NB	3.720	A	VR-023B	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS — $500 FINE FOR THROWING TRASH						1		X													
NB	3.850	C	VR-023B	24	30			5.00								1		X								INSTALL IN MIDDLE OF PULL OFF			E-144
NB	4.710	A	W11-2	30	30								1		X													
		A	W11-2	30	30	FYG	AHEAD	6.25								1		X									X	
		A	W16-9P	24	12	FYG		2.00																			X	
NB	5.350	A	VW-054L	30	30		HIDDEN DRIVE LEFT — HIDDEN DRIVE LEFT						1		X													
NB	5.415	A	VW-054L	30	30			6.25								1		X								INSTALL 350' NORTH OF ORIGINAL			E-154
NB	5.780	A	VW-285	30	30		FALLING ROCK						1		X													
NB	5.820	A	R2-1	24	30		SPEED LIMIT 50						1		X													
							SHEET TOTALS	29.50	0.00	0	0	0	8	0	0	4		60		0	0	0	0	0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	343.6	0.0	9.0	4.0	4.0	90	0.0	0.0	51		765.0		0			0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: NORWICH - FAIRLEE
PROJECT NUMBER: STPG SIGN (34)

FILE NAME: 10C334
PROJECT MANAGER: A.GAMBLE
DESIGNED BY: D.CROSSLEY
FAIRLEE US 5 NORTHBOUND 11

PLOT DATE: 5/2/2011
DRAWN BY: D.CROSSLEY
CHECKED BY: QAU
SHEET 50 OF 65