DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW SQUARE STEEL POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
FAIRLEE US 5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	6.900	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X													
SB	6.860	F	VW-054R	30	30		HIDDEN DRIVE RIGHT				1		1		X													
		~~F~~	~~S3-1~~	~~36~~	~~36~~	~~FYG~~		~~9.00~~								~~2~~		~~X~~								SIGN WAS NOT INSTALLED. NO LONGER A SCHOOL BUS STOP	X		
SB	~~6.810~~	F	VW-054R	30	30		HIDDEN DRIVE RIGHT					1				1		X								INSTALLSALVAGED SIGN ~~500'~~ +/- SOUTH OF ORIGINAL SIGN LOCATION 625			
SB	6.430	F	W1-2R	30	30		CURVE RIGHT						1		X													
		F	W13-1	18	18		35 MPH						1															
SB	6.400	F	VW-285	30	30		FALLING ROCK						1		X												WITH MILE MARKER			
		F	W1-2R	30	30		0050 0906 0640	6.25			1	1	1			1		X									X		
SB	6.300	F	VW-285	30	30			6.25								1		X								INSTALL 50'+/- NORTH OF PULL-OFF, MINIMUM 10' FROM POLE		5	
SB	5.600	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X													
SB	5.050	G	VR-017	24	24		LEGAL LOAD LIMIT 24,000 POUNDS	4.00								1		X								MOUNTAIN RD TH-10			E-141
SB	5.049	H	R1-1	24	24								1		X											MOUNTAIN RD TH-10			
		H	R1-1	30	30		STOP MOUNTAIN RD	6.25								1		X								WITH STREET SIGN	X		
SB	4.950	F	W11-2	30	30								1		X													
		F	W11-2	30	30	FYG	AHEAD	6.25								1		X									X		
							SHEET TOTALS	~~29.00~~ ~~38.00~~ SF	0.00 SF	0 EA	~~3~~ ~~1~~ EA	~~3~~ ~~1~~ EA	~~10~~ ~~8~~ EA	0 EA	0 EA	8 EA	120 FT		0 EA	0 LB	0 LB	0 LB	0 LB				
							TOWN DIRECTIONAL TOTALS	341.0	0.0	7.0	5.0	5.0	94	0.0	0.0	45	675.0		4	364.8								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: NORWICH - FAIRLEE
PROJECT NUMBER: STPG SIGN (34)

FILE NAME: 10C334
PROJECT MANAGER: A.GAMBLE
DESIGNED BY: D.CROSSLEY
FAIRLEE US 5 SOUTHBOUND 1

PLOT DATE: 5/2/2011
DRAWN BY: D.CROSSLEY
CHECKED BY: QAU
SHEET 52 OF 65