DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW SQUARE STEEL POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
FAIRLEE US 5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	VW-207P	24	18								1																
		F	W16-7	24	12								1																
		F	W11-2	30	30	FYG		6.25								1		X									X		
		F	VW-207P	24	18	FYG		3.00																				5	
		F	W16-7	24	12	FYG		2.00																			X		
SB	2.790	F	D1-1A	72	10		^ UP LAKE FAIRLEE 5						1		X														
		F	D1-1A	72	10		^ UP NORWICH 14						1																
SB	2.730	F	M3-3	24	12		ROUTE MARKER ASSEMBLY						1		X														
		F	M1-4	24	24								1																
		F	M6-3	21	15								1																
		F	M4-5	24	12								1																
		F	M1-1	24	24								1																
		F	M6-1	21	15								1																
		F	VD1-1A	72	12			6.00								0 ~~2~~				2	182.4				2	THINNING AND TRIMMING		4	
		F	VD1-1A	72	12			6.00																				4	
							SHEET TOTALS	23.25	0.00	0	0	0	10	0	0	1 ~~3~~		45		2	182.4	0	0	0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	341.0	0.0	7.0	5.0	5.0	94	0.0	0.0	45		675.0		4	364.8								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **NORWICH - FAIRLEE**
PROJECT NUMBER: **STPG SIGN (34)**

FILE NAME: **10C334**
PROJECT MANAGER: **A.GAMBLE**
DESIGNED BY: **D.CROSSLEY**
FAIRLEE US 5 SOUTHBOUND 7

PLOT DATE: **5/2/2011**
DRAWN BY: **D.CROSSLEY**
CHECKED BY: **QAU**