DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
DANBY NB/SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.004	D	R1-1	30	30								1		X											LILLY HILL RD. (TH-5)			
		D	R1-1	30	30		STOP	6.25								1		X									X		
SB	0.024	G	VD-024	60	7.5		DANBY/TINMOUTH TOWN LINE SIGN						1		X											NEW TOWN LINE SIGN TO BE INSTALLED ON OPPOSITE SIDE OF ROAD.			
SB	0.000	G	VD-024	60	7.5								1		X														
		G	VD-024	72	10		Pawlet | Danby	5.00								2		X								INSTALL DIRECTLY ACROSS FROM CENTER OF TOWN HIGHWAY.		4	
		G	VD-700	6	10		1330 1114 0533 / 1330 1106 0000	0.42																		INSTALL ON LH POST BELOW PAWLET.			E-138
		G	VD-700	6	10			0.42																		INSTALL ON RH POST BELOW DANBY.			E-138
							SHEET TOTALS	12.09	0.00	0	0	0	3	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	12.1	0.0	0	0	0	3	0	0	3		45.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
DANBY NB/SB SHEET 1

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **24** OF **61**