DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MIDDLETOWN SPRINGS SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	5.538	F	W1-1R	30	30		RIGHT TURN			1				X														
		F	W13-1	18	18		30 MPH ADVISORY			1																		
SB	5.293	F	W1-5R	30	30		RIGHT WINDING CURVES			1				X														
		F	W7-3A	24	18		NEXT 1 MILE			1																		
SB	5.194	F	W1-1L	30	30		LEFT TURN				1		1		X										MOVE 75 FEET SOUTH			
		F	W13-1	18	18		30 MPH ADVISORY				1		1															
		F	VD-700	6	10		5.20 MILE MARKER				1	1	1			1	X								REINSTALL 5.20 MILE MARKER ON NEW POST.			
SB	5.180	F	W1-1L	30	30		LEFT TURN					1				1		X							INSTALL 75 FEET SOUTH OF EXISTING			
		F	W13-1	18	18		30 MPH ADVISORY					1																
SB	5.140	F	W1-6L	48	24								1		X													
		F	W1-6L	48	24			8.00								2		X							INSTALL LARGE ARROWS BACK TO BACK ON SEPARATE POSTS.	X		
		E	W1-6R	48	24			8.00								2		X								X		
SB	5.120	E	W1-6R	48	24								1		X													
		E	W1-6R	48	24			8.00								2		X								X		
SB	5.115	F	W1-6L	48	24			8.00								2		X							INSTALL BETWEEN UTILITY POLE AND NORTH EDGE OF DRIVE	X		
							SHEET TOTALS	32.00	0.00	4	3	3	5	0	0	10		150.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	116.3	0.0	31	20	20	38	0	0	25		375.0		2		228.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
MIDDLETOWN SPRINGS SB SHEET 1

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **36** OF **61**