DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
PAWLET NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.025	A	M3-1	24	12		NORTH			1				X														
		A	M1-5	30	24		VERMONT 133			1																		
NB	0.070	A	W11-8	30	30								1	X														
		A	W11-8	30	30			6.25																		INSTALL NEW SIGN ON EXISTING POST.	X		
NB	0.120	A	R2-1	24	30		SPEED LIMIT 35						1		X													
		A	R2-1	24	30			5.00								1		X									X	
NB	0.400	A	OM3-R	12	36								1		X													
		A	OM3-R	12	36			3.00								1		X								INSTALL AT HEIGHT OF 4 FEET TO BOTTOM OF SIGN.	X		
		A	VD-701	6	8		BRIDGE MARKER				1	1	1													REINSTALL BELOW OBJECT MARKER.			
NB	0.410	B	OM3-L	12	36								1		X													
		B	OM3-L	12	36			3.00								1		X								INSTALL AT HEIGHT OF 4 FEET TO BOTTOM OF SIGN.	X		
NB	0.600	A	VW-202	30	30		TRUCKS ENTERING						1		X													
		A	VD-700	6	8		0.60 MILE MARKER				1	1	1			1	X									REINSTALL MILE MARKER ON NEW POST.			
NB	0.605	A	OM-3R	12	36								1		X													
		A	OM-3R	12	36			3.00								1		X								INSTALL AT HEIGHT OF 4 FEET TO BOTTOM OF SIGN.	X		
							SHEET TOTALS	20.25	0.00	2	2	2	8	0	0	5		75.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	233.8	0.0	4	4	4	50	0	0	39		585.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
PAWLET NB SHEET 1

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **9** OF **61**