| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **PAWLET NB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| NB | 1.100 | A | R2-1 | 24 | 30 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | A | R2-1 | 24 | 30 | | | 5.00 | | | | | | | | | | | | | | | | | | REPLACE SIGN. RETAIN POST. | X | | |
| NB | 1.150 | A | D1-1A | 72 | 10 | | <--- MIDDLETOWN 10 | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | D1-1A | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | VD1-1A | 72 | 12 | | | 6.00 | | | | | | | | 2 | | X | | | | | | | | 5 | |
| NB | 1.200 | A | VD-062B | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | A | VD-062B | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | | | | | | | | | | | | | | | | |
| NB | 1.240 | A | W1-1ML | 36 | 36 | | LEFT TURN SIGN NOT THERE | | | | | | ~~1~~ | | X | | | | | | | | | | | | | | |
| | | A | W13-1 | 18 | 18 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | VW1-1LM | 36 | 36 | | | 9.00 | | | | | | | | 2 | | X | | | | | | | | 7 | |
| | | A | W13-1 | 18 | 18 | | | 2.25 | | | | | | | | | | | | | | | | | | | | X | |
| NB | 1.275 | A | M3-1 | 24 | 12 | | NORTH | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | A | M1-5 | 30 | 24 | | VERMONT 133 | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | A | M6-1 | 21 | 15 | | LEFT ARROW | | | | | | 1 | | | | | | | | | | | | | | | | |
| NB | 1.295 | A | W1-6L | 48 | 24 | | | 8.00 | | | | | | | | 2 | | X | | | | | | | | | INSTALL NEW ON SOUTH SIDE OF POLE (W/ GUY WIRES AND WIRES INTO GROUND). | X | | |
| | | | | | | | SHEET TOTALS | 30.25 | 0.00 | 2 | 0 | 0 | ~~7~~ 8 | 0 | 0 | 6 | 90.0 | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | FT | | EA | LB | LB | LB | LB | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 233.8 | 0.0 | 4 | 4 | 4 | 50 | 0 | 0 | 39 | 585.0 | | 0 | 0.0 | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
PAWLET NB SHEET 3

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **11** OF **61**