DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
PAWLET NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	W13-1	18	18		40 MPH ADVISORY						1															
NB	2.380	A	W1-2L	30	30			6.25								1		X								INSTALL 325 FEET NORTH OF EXISTING ASSEMBLY AND SOUTH OF POLE	X		
		A	W13-1	18	18			2.25																			X		
NB	2.410	A	W1-8L	18	24								1	X															
		B	W1-8R	18	24								1	X															
		A	W1-8L	18	24			3.00																			~~INSTALL NEW SIGNS ON EXISTING POSTS.~~ EXISTING POSTS BENT	X		
		B	W1-8R	18	24			3.00																				X		
NB	2.430	A	W1-8L	18	24								1	X															
		B	W1-8R	18	24								1	X															
		A	W1-8L	18	24			3.00																			INSTALL NEW SIGNS ON EXISTING POSTS.	X		
		B	W1-8R	18	24			3.00																				X		
NB	2.440	A	W1-8L	18	24		CHEVRON						1		X														
		B	W1-8R	18	24		CHEVRON						1																
NB	2.450	A	W1-8L	18	24			3.00								1		X									INSTALL BACK TO BACK ON SEPARATE POSTS.	X		
		B	W1-8R	18	24			3.00								1		X									INSTALL NORTH OF EXISTING TO MAINTAIN 100 FT SPACING OF CHEVRON ASSEMBLIES.	X		
							SHEET TOTALS	26.50	0.00	0	0	0	7	0	0	3		45.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	233.8	0.0	4	4	4	50	0	0	39		585.0		0		0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
PAWLET NB SHEET 5

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **13** OF **61**