DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
PAWLET NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.710	C	VR-017	24	30								1		X											KELLEY HILL RD (TH-14)			
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X										6	
		C		24	30		TOWN'S REDUCED SPEED AHEAD						1																
NB	2.715	D	R1-1	30	30								1	X												KELLEY HILL RD (TH-14)			
		D	R1-1	30	30		STOP	6.25																		INSTALL NEW SIGN ON EXISTING POST.	X		
NB	2.910	A	W1-2R	30	30		RIGHT CURVE						1		X														
		A	W13-1	18	18		40 MPH ADVISORY						1																
NB	2.960	A	W1-2R	30	30			6.25								1		X								INSTALL 250 FEET NORTH OF EXISTING AND ON EDGE OF CEMETERY LAWN.	X		
		A	W13-1	18	18		40 MPH	2.25																		THINNING AND TRIMING	X		
NB	2.995	A	VW-202	30	30								1		X														
		A	VW-202	36	36		TRUCKS ENTERING	9.00								2		X										7	
NB	3.400	A	W11-4	30	30		MM 3.4	6.25			I	I	I		I	1		X								INSTALL AT 3.40 MILE MARKER	X		
NB	3.540	A	W1-2L	30	30		LEFT CURVE						~~1~~		X											LEFT CURVE SIGN MISSING			
		A	W13-1	18	18		NOT THERE - NO REMOVAL 35 MPH ADVISORY						1																
NB	3.580	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
							SHEET TOTALS	35.00 SF	0.00 SF	0 EA	~~0~~ EA	~~0~~ EA	9 EA	0 EA	0 EA	5 EA		75.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	233.8	0.0	4	4	4	50	0	0	39		585.0		0	0.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
PAWLET NB SHEET 6

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **14** OF **61**