DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MIDDLETOWN SPRINGS NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	W13-1	18	18		40 MPH ADVISORY				1	1	1															
NB	2.809	A	W3-5	36	36		SPEED REDUCTION			1				X														
NB	2.860	A	VD-018	30	18		MIDDLETOWN SPRINGS			1				X														
NB	2.921	A	R2-1	24	30		SPEED LIMIT 40			1				X														
NB	3.111	A	R2-1	24	30		SPEED LIMIT 35			1				X														
NB	3.315	A	R2-1	24	30		SPEED LIMIT 35				1	1	1		X	1		X									REMOVE AND REINSTALL SALVAGED SIGN. REPLACE POST.		
NB	3.499	A	R2-1	24	30		SPEED LIMIT 35				1	~~1~~ 2	~~1~~ 2		X	1		X									REMOVE AND REINSTALL SALVAGED SIGN. REPLACE POST.	THINNING AND TRIMMING	
NB	3.640	C	VR-017	24	30								1	X													MONTVERT RD (TH-26)		
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																			INSTALL NEW SIGN ON EXISTING POST.		6
NB	3.640	D	R1-1	30	30		STOP			1				X													MONTVERT RD (TH-26)		
NB	3.653	D	R1-1	30	30		STOP			1				X													MONTVERT RD (TH-26)		
NB	3.696	A	S1-1	30	30		SCHOOL			1				X														
		A	W16-9	24	12		AHEAD			1																		
NB	3.724	A	M2-1	21	15		JCT				1	1	1		X	1		X									REMOVE AND REINSTALL SALVAGED SIGNS. REPLACE POST.		
		A	M1-6	30	24		ROUTE 140				1	1	1															
							SHEET TOTALS	5.00	0.00	8	5	~~5~~ 6	~~6~~ 7	0	0	3	45.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	44.1	0.0	42	13	13	22	0	0	16	240.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340** PLOT DATE: **5/6/2011**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED **A. GAMBLE**
MIDDLETOWN SPRINGS NB SHEET 2 SHEET **31** OF **61**