DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MIDDLETOWN SPRINGS SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	5.080	F	W1-6L	48	24		• NOT THERE - NO REMOVAL LEFT LARGE ARROW						~~1~~		X											REMOVE DAMAGED SIGN DEBRIS FROM SOUTH SIDE OF DRIVE.			
SB	5.000	G	VR-017	24	30								1		X											HALEY RD. (TH-10)			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24.000 POUNDS	5.00								1		X										6	
		G		24	24		TOWN'S DEAD END SIGN				1	1	1			1		X								INSTALL 50 FEET NORTHERLY ON TOWN HIGHWAY AND ON SEPARATE POST.			
SB	4.988	H	R1-1	30	30		STOP				1	1	1		X	1		X								HALEY RD. (TH-10) REINSTALL SIGN ON NEW POST.			
SB	4.620	F	W1-6L	48	24		LEFT LARGE ARROW					1				2		X								INSTALL 75 FEET NORTH OF EXISTING LARGE ARROW			
SB	4.605	F	W1-6L	48	24		LEFT LARGE ARROW				1		1		X											RELOCATE 75 FEET NORTH.			
SB	4.603	E	W1-6R	48	24		RIGHT LARGE ARROW			1				X															
SB	4.600	G	VR-017	24	30								~~1~~ 2		X											DUDLEY RD. (TH-9)			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24.000 POUNDS	5.00								1		X										6	
		G	R2-1				TOWN'S SPEED LIMIT SIGN				1	1	1													REINSTALL BELOW NEW LEGAL LOAD SIGN.			
SB	4.593	H	R1-1	30	30		STOP				1	1	1		X	1		X								DUDLEY RD. (TH-9) REINSTALL SIGN ON NEW POST BEFORE MAILBOXES AND LARGE TREE.			
SB	4.355	F	R2-1	24	30		SPEED LIMIT 40			1				X															
SB	4.299	F	VD-018	30	18		VILLAGE SIGN				1	1	1		X	1		X								REINSTALL SIGN ON NEW POST.			
SB	4.171	F	R2-1	24	30		SPEED LIMIT 35			1				X															
							SHEET TOTALS	10.00	0.00	3	6	6	9	0	0	8		120.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	116.3	0.0	31	20	20	38	0	0	25		375.0		2	228.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340** PLOT DATE: **5/6/2011**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED **A. GAMBLE**