DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MIDDLETOWN SPRINGS SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	3.860	H	R1-1	30	30								1	X												ROUTE 140 (TH-1)			
		H	R1-1	30	30			6.25																		INSTALL NEW SIGNS ON EXISTING POST.	X		
		H	R1-3	12	6		4-WAY						1																
		H	R1-3P	18	6			0.75																			X		
SB	3.844	F	M3-3	24	12		SOUTH			1				X															
		F	M1-5	30	24		VERMONT 133			1																			
SB	3.835	F	S1-1	30	30		SCHOOL			1				X															
		F	W16-9	24	12		AHEAD			1																			
SB	3.790	F	S1-1	30	30		SCHOOL			1				X															
		F	W16-7	24	12		DIAGONAL ARROW			1																			
SB	3.785	G	VR-017	24	30								1	X												SCHOOL HOUSE RD. (TH-23)	THINNING AND TRIMMING		
		G	VR-017	24	30			5.00																		INSTALL NEW SIGN ON EXISTING POST.	6		
SB	3.780	H	R1-1	30	30		STOP			1				X												SCHOOL HOUSE RD. (TH-23)			
SB	3.740	F	VR-020	24	30								1	X															
		F	VR-020	24	30			5.00																		INSTALL NEW SIGN ON EXISTING POST.	6		
SIGN SUMMARY SHEET							SHEET TOTALS	17.00	0.00	7	0	0	4	0	0	0	0.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	116.3	0.0	31	20	20	38	0	0	25	375.0		2	228.0								

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340** PLOT DATE: **5/6/2011**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED **A. GAMBLE**
MIDDLETOWN SPRINGS SB SHEET 5 SHEET **40** OF **61**