DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
MIDDLETOWN SPRINGS SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	W11-5	30	30			6.25								1		X								INSTALL 200 FEET NORTH OF POLE # 342/10T/7/46.	X		
SB	1.380	F	W11-7	30	30		EQUESTRIAN				1	1	1		X	1		X								REINSTALL SIGN ON NEW POST.			
SB	1.303	F	W1-4R	30	30		RIGHT REVERSE CURVE			1				X															
SB	0.706	F	W1-2L	30	30		LEFT CURVE				1		1		X											RELOCATE SIGN ASSEMBLY 300 FEET SOUTH			
		F	W13-1	18	18		40 MPH ADVISORY				1		1																
SB	0.649	F	W1-2L	30	30		LEFT CURVE					1				1		X								INSTALL SIGN ASSEMBLY 300 FEET SOUTH OF EXISTING.			
		F	W13-1	18	18		40 MPH ADVISORY					1																	
SB	0.615	F	W1-6L	48	24		LEFT LARGE ARROW			1				X															
		E	W1-6R	48	24		RIGHT LARGE ARROW			1																			
							SHEET TOTALS	6.25	0.00	3	3	3	3	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	116.3	0.0	31	20	20	38	0	0	25		375.0		2		228.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: PAWLET - WEST RUTLAND
PROJECT NUMBER: STPG SIGN(37)

FILE NAME: 10C340
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
MIDDLETOWN SPRINGS SB SHEET 7

PLOT DATE: 5/6/2011
DRAWN BY: J. KELLY
CHECKED A. GAMBLE
SHEET 42 OF 61