DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
TINMOUTH NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.150	C	VD-024	54	7.5								1		X														
		C	VD-024	72	10		Tinmouth | Middletown Springs	5.00								2		X										4	
		C	VD-700	6	10		1330 1124 | 1330 1111	0.42																		INSTALL ON LH POST BELOW TINMOUTH. LEAVE BOTTOM SET OF NUMBERS BLANK.			E-138
		C	VD-700	6	10			0.42																		INSTALL ON RH POST BELOW MIDDLETOWN SPRINGS. LEAVE BOTTOM SET OF NUMBERS BLANK.			E-138
NB	2.171	A	M2-1	21	15		JCT			1				X															
		A	M3-2	24	12		EAST			1																			
		A	M1-6	30	24		ROUTE 140			1																			
NB	2.240	A	D1-1A	72	12		<--- (45 DEG) IRA 5			1				X															
		A	D1-1A	72	12		<--- (45 DEG) WEST RUTLAND 9			1																			
		A	D1-1A	72	12		TINMOUTH 3 --->			1																			
		A	D1-1A	72	12		WALLINGFORD 9 --->			1																			
NB	2.275	A	M3-1	24	12		NORTH				1	1	1		X	2		X									REMOVE AND SALVAGE SIGNS AND FRAME. INSTALL ON NEW POSTS.			
		A	M1-5	30	24		VERMONT 133				1	1	1																
		A	M6-2	21	15		<--- LEFT (45 DEG)				1	1	1																
		A	M3-2	24	12		EAST				1	1	1																
							SHEET TOTALS	5.84	0.00	7	4	4	5	0	0	4		60.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	35.1	0.0	11	6	6	10	0	0	8		120.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
TINMOUTH NB SHEET 1

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **43** OF **61**