DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
TINMOUTH SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	3.150	F	VW-054R	30	30								1	X												THINNING AND TRIMMING			
		F	VW-054R	30	30			6.25																		INSTALL NEW SIGN ON EXISTING POST.		7	
SB	3.130	F	VW-407A	30	30		THINNING AND TRIMMING SCHOOL BUS ENTERING						1		X											THINNING AND TRIMMING			
		F	VS3-4	36	36	FYG		9.00								2		X									7	
SB	2.600	F	S3-1	36	36	FYG		9.00								2		X								INSTALL 500 FEET NORTH OF DRIVE #74, AT 2.60 MILE MARKER.	X		
SB	3.089	F	W11-7	30	30		EQUESTRIAN				1	1	1		X	1		X								REINSTALL SIGN ON NEW POST.			
SB	2.480	F	W3-5	36	36		SPEED REDUCTION 40			1				X														
SB	2.435	F	M2-1	21	15		JCT				1	1	1		X	1		X								REINSTALL SIGNS ON NEW POST.			
		F	M3-2	24	12		EAST				1	1	1															
		F	M1-6	30	24		ROUTE 140				1	1	1															
SB	2.397	F	W1-10R	30	30		MODIFIED RIGHT CURVE			1				X														
SB	2.450	G	VR-023B	24	30		• NOT THERE - NO REMOVAL $500 FINE FOR THROWING TRASH						~~1~~		X													
SB	2.359	F	D1-1A	72	12		<--- TINMOUTH 3			1				X														
		F	D1-1A	72	12		<--- WALLINGFORD 9			1																		
		F	D1-1A	72	12		MIDDLETOWN SPRINGS 2 ---> (45 DEG)			1																		
							SHEET TOTALS	24.25	0.00	5	4	4	~~6~~ 7	0	0	6	90.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	32.3	0.0	22	4	4	8	0	0	8	120.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
TINMOUTH SB SHEET 1

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **45** OF **61**