DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
IRA NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.000	C	VD-024	60	7.5								1		X													
		C	VD-024	72	10		Ira / Tinmouth	5.00								2		X										4	
		C	VD-700	6	10		1330 1109 0000 / 1330 1124	0.42																			INSTALL ON LEFT POST BELOW IRA.			E-138
		C	VD-700	6	10			0.42																			INSTALL ON RIGHT POST BELOW TINMOUTH. LEAVE BOTTOM SET OF NUMBERS BLANK.			E-138
NB	0.260	A	W1-2R	30	30		THINNING AND TRIMMING RIGHT CURVE				1		1		X												MOVE 370 FEET NORTH.			
NB	0.330	A	W1-2R	30	30		RIGHT CURVE					1				1		X									INSTALL 370 FEET NORTH OF EXISTING AND AT EDGE OF MOWED LAWN.	X		
NB	1.405	A	S3-1	36	36	FYG		9.00								2		X									INSTALL 50 FEET SOUTH OF DRIVE #3399.	X		
NB	2.002	C	VR-017	24	30		LLL 24,000 LBS (MISSING)						~~1~~		X											TOPPIN RD. (TH-6)			
		C	VR-017	24	30			5.00								1		X											6	
NB	2.005	D	R1-1	30	30		STOP			1				X													TOPPIN RD. (TH-6)			
NB	2.540	A	W3-5	36	36		SPEED REDUCTION			1				X																
NB	2.597	A	VD-018	30	18		IRA			1				X																
NB	2.650	A	R2-1	24	30		SPEED LIMIT 40			1				X																
NB	2.990	A	R2-1	24	30								1		X															
		A	R2-1	24	30			5.00								1		X											X		
SIGN SUMMARY SHEET							SHEET TOTALS	24.84	0.00	4	1	1	~~3~~ 4	0	0	7		105.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	60.6	0.0	5	4	4	17	0	0	14		210.0		0	0.0								

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340** PLOT DATE: **5/6/2011**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED **A. GAMBLE**
IRA NB SHEET 1 SHEET **48** OF **61**