DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
IRA SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	4.745	F	W1-2L	30	30		LEFT CURVE						1		X													
		F	W13-1	18	18		35 MPH ADVISORY						I		X													
SB	4.715	F	W1-2L	30	30			6.25								1		X									INSTALL 160 FEET SOUTH OF EXISTING AND 10 FEET NORTH OF UTILITY POLE.	X		
		F	W13-1	18	18			2.25																			X		
SB	4.668	F	W1-6L	48	24								1		X														
		F	W1-6L	48	24			8.00								2		X										X	
SB	4.617	G	VR-017	24	30								1		X												PYKA RD. (TH-3)			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X											6	
SB	4.610	H	R1-1	30	30								1		X												PYKA RD. (TH-3)			
		H	R1-1	30	30		STOP	6.25								1		X									REINSTALL STREET NAME SIGN ABOVE NEW SIGN.	X		
SB	3.900	F	W1-2L	30	30		LEFT CURVE						1		X													
		F	W13-1	18	18		35 MPH ADVISORY						1															
SB	3.805	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1	X														
		F	W1-2L	30	30			6.25																			INSTALL NEW SIGNS ON EXISTING POST.	X		
		F	W13-1	18	18			2.25																				X	
							SHEET TOTALS	36.25	0.00	0	0	0	~~8~~ 7	0	0	5	75.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	126.5	0.0	2	0	0	21	0	0	13	195.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
IRA SB SHEET 1

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **51** OF **61**