DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CLARENDON NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.000	C	VD-024	60	7.5								1		X													
		C	VD-024	72	10		Clarendon | Ira 1330 1105 0000 | 1330 1109 0478	5.00								2		X									4	
		C	VD-700	6	10			0.42																		INSTALL ON LEFT POST BELOW CLARENDON.			E-138
		C	VD-700	6	10			0.42																		INSTALL ON RIGHT POST BELOW IRA.			E-138
NB	0.245	A	R2-1	24	30								1	X												THINNING AND TRIMMING			
		A	R2-1	24	30		SPEED LIMIT 40	5.00																		INSTALL NEW SIGN ON EXISTING POST.	X		
NB	0.735	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		X													
		A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1															
NB	0.742	A	S3-1	36	36			9.00								2		X								INSTALL 200 FEET SOUTH OF CLARENDON SPRINGS D-BOARD.	THINNING AND TRIMMING X		
NB	0.780	A	D1-1A	54	7.5								1		X											THINNING AND TRIMMING			
		A	VD1-1A	72	12		Clarendon Springs 1 →	6.00								2		X										5	
NB	0.840	C	VR-017	24	30		(MISSING) SPEED LIMIT 35				1	2	~~1~~ 2		X													
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00				1	2			1		X								WALKER MOUNTAIN RD (TH-3). INSTALL EAST OF TRIANGLE.		6	
NB	0.845	D	R1-1	30	30		STOP			1				X												LOCATED IN ISLAND.			
NB	0.846	A	W1-6L	48	24								1	X														
							SHEET TOTALS	30.84	0.00	1	~~0~~ 1	~~0~~ 1	~~7~~ 8	0	0	7	105.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	73.8	0.0	2	1	1	11	0	0	14	210.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340** PLOT DATE: **5/6/2011**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED **A. GAMBLE**
CLARENDON NB SHEET 1 SHEET **54** OF **61**