DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
WEST RUTLAND SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	0.700	F	R2-1	24	30								1		X													
		F	VR-039	24	18			3.00								1		X								SOUTH OF INTERSECTION WITH SKYLINE DRIVE.		6	
		F	R2-1	24	30			5.00																			X		
		E	VR-038	24	18		STATE HIGHWAY ENDS						1																
		E	VR-040	24	24		THROUGH WAY ENDS HERE						1																
SB	0.375	F	W1-2R	30	30		RIGHT CURVE						1		X														
		F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1																
SB	0.365	F	W1-2R	30	30	FY		6.25								1		X								INSTALL 50 FEET SOUTH OF EXISTING RIGHT CURVE SIGN AND AT NORTH EDGE OF DRIVE.		X	
SIGN SUMMARY SHEET							SHEET TOTALS	14.25	0.00	0	0	0	5	0	0	2	30.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	14.3	0.0	0	0	0	5	0	0	2	30.0		0	0.0								

PROJECT NAME: **PAWLET - WEST RUTLAND**
PROJECT NUMBER: **STPG SIGN(37)**

FILE NAME: **10C340**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WEST RUTLAND SB SHEET 1

PLOT DATE: **5/6/2011**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **60** OF **61**