









DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)				(LB / FT)								
<b>READING NB</b>							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS							
NB	0.546	A	S1-1	30	30	FYG	SCHOOL SYMBOL					1	X										RETAIN THE EXISTING FLANGE POST AND SINGLE FLASHING BEACON						
		A	W16-9P	24	12	FYG	AHEAD (PLAQUE)					1											WILL NOT BE REPLACED						
		A	S1-1	36	36	FYG		9.00															BOTH SIGNS HAVE FLUORESCENT YELLOW-GREEN SHEETING (FYG)	X					
		A	S4-3P	24	8	FYG		1.33															NEW PLAQUE	X					
NB	0.592	A	D1-1E	72	20							1	X										BEHIND RAIL						
		A	VD1-2®	72	20			10.00															NOTE: NEW SIGN HAS UPPER AND LOWER CASE LETTERS		8				
NB	0.635	A	S1-1	30	30	FYG	SCHOOL SYMBOL					1	X										<del>THIS ASSEMBLY TO BE REPLACED 90 FT ± NORTH</del>						
		A	W16-7P	24	12	FYG	DIAGONAL ARROW (PLAQUE)					1											(NEW SIGNS WILL BE DIFFERENT SIZES)						
NB	<del>0.635</del> 0.652	A	S1-1	36	36	FYG		9.00					X										<del>INSTALL THE NEW SIGNS ON ONE POST 90 FT ± NORTH OF MP 0.635, IN THE GRASSY STRIP BETWEEN THE...</del>	X					
		A	W16-7P	21	15	FYG		2.19															<del>RESIDENTIAL AND SCHOOL DRIVES ADJACENT TO THE CROSSWALK.</del>	X					
NB	0.770	A	R2-1	24	30							2																	
NB	0.788	A	D1-1A	72	10		<--- SOUTH READING 3					1	X																
		A	D1-1A	72	10		<--- TYSON 10					1																	
		A	VD1-1A	72	12			6.00															NOTE: THE NEW SIGNS HAVE UPPER / LOWER CASE LETTERS.		4				
		A	VD1-1A	72	12			6.00															NOTE: CHANGE IN SIGN CODES		4				
<b>SIGN SUMMARY SHEET</b>							SHEET TOTALS	43.52	0.00	<del>2</del> +	0	0	7	0	0	<del>4</del> -	<del>51.25</del> 75.00					PROJECT NAME: <b>READING-WOODSTOCK</b>							
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	243.68	0.00	8	2	2	43	0	0	38	570.00					PROJECT NUMBER: <b>STPG SIGN (38)</b>							
																						FILE NAME: <b>READING VT-106 NB</b>	PLOT DATE: <b>4/7/2011</b>						
																						PROJECT MANAGER: <b>A. GAMBLE</b>	DRAWN BY: <b>M. MILLER</b>						
																						DESIGNED BY: <b>M. MILLER</b>	CHECKED BY: <b>A. GAMBLE</b>						
																						READING VT-106 NORTHBOUND 2	SHEET <b>10</b> OF <b>49</b>						