



DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)				(LB / FT)								
<b>READING NB</b>							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS							
NB	0.841	A	M3-1	24	12			2.00							1	13.5' X							NEW ASSEMBLY. INSTALL 50 FT ± NORTH OF THE JCT WITH TYSON RD (TH-1); GREEN ON WHITE;	X					
		A	M1-5	30	24			5.00															MAINTAIN 5 TO 10 FT ± IN FRONT OF POLE # 40/87/CTC-VT/23/4.			E-136B			
NB	0.876	A	R2-1	24	30		SPEED LIMIT 35		1														MINOR BRANCH THINNING (LILAC BUSH) LIKELY REQUIRED						
NB	1.031	A	R2-1	24	30		SPEED LIMIT 35		1														MINOR BRUSH CUTTING MAY BE REQUIRED						
NB	1.216	A	R2-1	24	30		SPEED LIMIT 40		1																				
NB	1.554	A	R2-1	24	30		SPEED LIMIT 50		1														MINOR BRUSH CUTTING MAY BE REQUIRED						
NB	1.616	A	W11-8	30	30		FIRE ENGINE SYMBOL			1		1																	
		A	W11-8	30	30		FIRE ENGINE SYMBOL				1				1	13.5' X							SALVAGE THIS SIGN (2006) ONTO A NEW POST						
NB	1.656	A	VD-062B	72	16		BUSINESS DIRECTIONAL SIGN		1														HUMANE SOCIETY						
NB	1.698	A	M2-1	21	15		JCT					1																	
		A	M1-5	24	24		VT-44					1																	
		A	M2-1	21	15			2.19							1	14.0' X							GREEN ON WHITE	X					
		A	M1-5	24	24			4.00																		E-136B			
NB	1.740	A	D1-1A	72	10		SOUTH WOODSTOCK 8 ^					1											REMOVE ALL SIGNS AND BOTH POSTS; NOTE THAT THE NEW SIGNS WILL LOOK DIFFERENT						
		A	D1-1A	72	10		WOODSTOCK 13 ^					1																	
<b>SIGN SUMMARY SHEET</b>							<b>SHEET TOTALS</b>	13.19	0.00	5	1	1	5	0	0	3	41.0' <del>45.00</del>							PROJECT NAME: <b>READING-WOODSTOCK</b>					
VERMONT AGENCY OF TRANSPORTATION							<b>TOWN DIRECTIONAL TOTALS</b>	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT							PROJECT NUMBER: <b>STPG SIGN (38)</b>					
							243.68	0.00	8	2	2	43	0	0	38	570.00							FILE NAME: <b>READING VT-106 NB</b>						
																							PLOT DATE: <b>4/7/2011</b>						
																							DESIGNED BY: <b>M. MILLER</b>						
																							PROJECT MANAGER: <b>A. GAMBLE</b>						
																							CHECKED BY: <b>A. GAMBLE</b>						
																							READING VT-106 NORTHBOUND 3						
																							SHEET <b>11</b> OF <b>49</b>						