












DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL				
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER	
																	(LB / FT)				(LB / FT)									
<b>READING NB</b>							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS								
NB	4.981	A	W1-4R	30	30		 REVERSE CURVE RIGHT																1060 1414 0500				TOO FAR BACK, TO BE REPLACED NORTH AT MP 5.050; DISCARD THE MILE MARKER SIGN			
NB	5.050	A	W1-4R	30	30			6.25																			INSTALL 365 FT ± NORTH OF MP 4.981	X		
NB	6.070	A	W2-2	30	30			6.25																			INSTALL ACROSS FROM THE BEGIN OF GUARDRAIL FOR THE SB LANE; 280 FT ± SOUTH OF THE JCT w/ CAPER HILL RD	X		
		A	W16-8P	24	15		 Caper Hill Rd	2.50																						7
NB	6.113	C	VR-017	24	30		 LEGAL LOAD LIMIT 24,000 POUNDS																				CAPER HILL RD (TH-24/25)			
		C	VR-017	24	30			5.00																						6
NB	6.127	D	R1-1	30	30		 STOP																1060 1414 0612				CAPER HILL RD (TH-24/25)			
		D	R1-1	30	30			6.25																						X
NB	<del>6.176</del> 6.168	A	M3-1	24	12		 NORTH VERMONT 106	2.00																			GREEN ON WHITE	X		
		A	M1-5	30	24			5.00																			INSTALL BEHIND RAIL 246 FT ± NORTH OF THE JCT WITH CAPER HILL RD (TH-24)			E-136B
NB	6.227	A	R2-1	24	30		 SPEED LIMIT 50	5.00																			INSTALL BEHIND RAIL 340 FT ± NORTH OF THE NEW ROUTE MARKER AT MP 6.168	X		
NB	6.770	A	W7-1	30	30		 7%	6.25																			INSTALL ACROSS FROM ± THE SOUTH END OF THE SB GRAVEL PULLOFF, AT THE TOP OF THE HILL ±	X		
		A	W7-3A	24	18		 NEXT 1 MILE	3.00																						7
NB	7.174	A	R2-1	24	30		 SPEED LIMIT 50	5.00																			INSTALL ADJACENT TO THE BEGIN OF THE NB PASSING ZONE, 730 FT ± SOUTH OF THE EXISTING SIGN AT MP 7.312	X		
NB	7.312	A	R2-1	24	30		SPEED LIMIT 50																							X
<b>SIGN SUMMARY SHEET</b>							SHEET TOTALS	52.50	0.00	0	1	1	6	0	0	8	102.25							PROJECT NAME: READING-WOODSTOCK PROJECT NUMBER: STPG SIGN (38)						
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	243.68	0.00	8	2	2	43	0	0	38	570.00							FILE NAME: READING VT-106 NB PROJECT MANAGER: A. GAMBLE DESIGNED BY: M. MILLER READING VT-106 NORTHBOUND 7						
																							PLOT DATE: 4/7/2011 DRAWN BY: M. MILLER CHECKED BY: A. GAMBLE SHEET 15 OF 49							