DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WOODSTOCK NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	R2-1	30	36			7.50								1	14.75' X								NEW SIGN IS LARGER		6	
NB	1.117	A	W11-7	30	30		HORSE WITH RIDER (SYMBOL)						1		X													
		A	W7-3A	24	18		NEXT 2 MILES (PLAQUE)						1															
		A	W11-7	30	30			6.25								1	14.25' X									X		
		A	W7-3A	24	18			3.00																		X		
NB	1.182	A	R2-1	24	30								1		X														
		A	R2-1	24	30			5.00								1	13.0' X									X		
NB	1.270	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		X											TO BE REPLACED FURTHER AHEAD AT MP 1.308; THE SPEED ADVISORY PLAQUE WILL NOT BE REPLACED; **DISCARD THE MILE MARKER**			
		A	W13-1	18	18		1060 1424 0128 35-MPH (PLAQUE)						~~1~~ 2															
NB	1.308	A	W1-4R	30	30			6.25								1	13.5' X								INSTALL THIS ASSEMBLY 200 FT ± NORTH OF MP 1.270	X		
NB	1.440	A	W3-5	36	36		SPEED REDUCTION 30-MPH						1		X										SIGN AND POSTS ~~MISSING?~~ THIS SIGN WAS INSTALLED 290 FT± SOUTH OF THE EXISTING VILLAGE SIGN AT MP 1.495			
		A	VD-018	30	18		1060 1424 0144 South Woodstock Woodstock 5	3.75			1	1	1			1	12.0' X								INSTALL THE NEW VILLAGE SIGN IN THE SAME POSITION AS THE REMOVED (MISSING?) SPEED REDUCTION SIGN		8	
NB	1.495	A	VD-018	30	18		SOUTH WOODSTOCK WOODSTOCK 5						1		X											THIS LOCATION TO BE REFERENCED FOR THE NEXT SIGN AHEAD			
NB	1.514	A	W3-5	36	36			9.00								2	13.75' 14.25' X								INSTALL 100 FT ± NORTH OF THE VILLAGE SIGN THAT WAS JUST REMOVED	X		
NB	1.550	A	VR-020	24	30		NO PARKING ON TRAVELED LANE						1		X													
							SHEET TOTALS	40.75 SF	0.00 SF	0 EA	~~1~~ 0 EA	~~1~~ 0 EA	~~10~~ 7 EA	0 EA	0 EA	7 EA	~~95.5'~~ 105.00 FT											
							TOWN DIRECTIONAL TOTALS	428.09	0.0	2	9	9	94	0	0	87	1305.00											

REMOVED (PREVIOUSLY ON THIS PROJECT)

MILE MARKER SALVAGED ONTO NEW POST.

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: READING- WOODSTOCK
PROJECT NUMBER: STPG SIGN (38)

FILE NAME: WOODSTOCK VT-106 NB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
WOODSTOCK VT-106 NORTHBOUND 2

PLOT DATE: 4/7/2011
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE
SHEET 27 OF 49