





DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)				(LB / FT)								
WOODSTOCK NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS							
NB	2.927	A	D3-1	30	8		BRYANT RD TH-63 (STREET NAME SIGN)				1				1			14.0'						SALVAGE FROM MP 2921; FACES NB TRAFFIC					
		B	D3-1	30	8		BRYANT RD TH-63 (STREET NAME SIGN)				1													SALVAGE FROM 2.942; FACES SB TRAFFIC (INSTALL THE TWO SIGNS BACK-TO-BACK)					
NB	2.942	D	R1-1	30	30		STOP					1			X									BRYANT RD (TH-63); NORTHERLY APPROACH					
		C	D3-1	30	8		BRYANT RD TH-63 (STREET NAME SIGN INSTALLED ON BACK OF THE STOP SIGN)																	THE STREET NAME SIGN TO BE SALVAGED FROM HERE ONTO A NEW STAND-ALONE POST AT MP 2.927±					
		D	R1-1	30	30			6.25							1			12.75'							X				
NB	2.963	A	W5-2	30	30							1			X									THE NEW SIGN IS LARGER PER THE 2009 MUTCD			X		
		A	W5-2	36	36			9.00							2			14.5'							X				
NB	3.006	A	W1-6L	48	24		LARGE ARROW LEFT					1			X									FACES NB TRAFFIC					
		B	W1-6R	48	24		LARGE ARROW RIGHT					1												FACES SB TRAFFIC					
		A	W1-6L	48	24			8.00							2			12.75'							X				
		B	W1-6R	48	24		 (BACK-BACK)	8.00										13.5'						INSTALLED BACK-TO-BACK			X		
NB	3.016	A	OM-3R	12	36		OBJECT MARKER					1			X									FACES NB TRAFFIC					
		A	VD-701	6	8		BRIDGE / 24 / VT 106				1													THE BRIDGE NUMBER PLAQUE TO BE SALVAGED TO UNDER THE NEW OBJECT MARKER					
		A	OM-3R	12	36			3.00							1			11.25'						INSTALL AT 4 FT VERTICAL CLEARANCE MEASURED FROM EDGE OF ROAD TO BOTTOM OF SIGN			X		
		A	VD-701	6	8		BRIDGE / 24 / VT 106					1												SALVAGE TO UNDER THE NEW OBJECT MARKER					
SIGN SUMMARY SHEET							SHEET TOTALS	34.25	0.00	0	2	3	7	0	0	7	93.75							PROJECT NAME: READING- WOODSTOCK					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT							PROJECT NUMBER: STPG SIGN (38)					
							428.09	0.0	2	9	9	94	0	0	87	1305.00							FILE NAME: WOODSTOCK VT-106 NB	PLOT DATE: 4/7/2011					
																						PROJECT MANAGER: A. GAMBLE	DRAWN BY: M. MILLER						
																						DESIGNED BY: M. MILLER	CHECKED BY: A. GAMBLE						
																						WOODSTOCK VT-106 NORTHBOUND 8	SHEET 33 OF 49						