








DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)				(LB / FT)								
WOODSTOCK SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS							
SB	5.507	F	W5-2	36	36			9.00							2	14.25' 14.5' X							INSTALL 400 FT ± IN ADVANCE (NORTH OF) THE OBJECT MARKER AT MP 5.431	X					
SB	5.431	F	OM-3R	12	36		OBJECT MARKER																FACES SB TRAFFIC						
		A	VD-701	6	8					1	1												THE BRIDGE NUMBER PLAQUE TO BE SALVAGED						
		F	OM-3R	12	36			3.00							1	10.5' X							INSTALL AT 4 FT VERTICAL CLEARANCE MEASURED FROM EDGE OF ROAD TO BOTTOM OF SIGN	X					
		A	VD-701	6	8		BRIDGE / 29 / VT 106				1												SALVAGE THE BRIDGE PLAQUE TO UNDER THE NEW OBJECT MARKER						
SB	5.418	E	OM-3L	12	36																		FACES NB TRAFFIC						
		E	OM-3L	12	36			3.00							1	10.5' X							INSTALL AT 4 FT VERTICAL CLEARANCE MEASURED FROM EDGE OF ROAD TO BOTTOM OF SIGN	X					
SB	5.194	F	VW-060	30	30			6.25							1	13.25' X							INSTALL 25 FT ± NORTH OF AND ACROSS FROM THE LEFT-SIDE RED BARN (BARN IS JUST NORTH OF DRIVE #2033)			E-154			
SB	4.437	F	W1-4R	30	30																		TO BE REPLACED AT MP 4.375 ^{4.405} 325 FT ± AHEAD ¹⁵⁵						
		F	W13-1	18	18																								
SB	4.405 4.375	F	W1-4R	30	30			6.25							1	15.0' X							INSTALL 325 ¹⁵⁵ FT ± SOUTH OF THE PREVIOUS LOCATION AT 4.437, 50 FT ± IN ADVANCE OF THE GRAVEL DRIVE	X					
		F	W13-1	18	18			2.25															NOTE INCREASE IN ADVISORY SPEED	X					
SB	3.785	F	W3-5	36	36																		TO BE REPLACED AT MP 3.773						
SB	3.773	F	W3-5	36	36			9.00							2	14.0' 14.5' X							INSTALL 65 FT ± SOUTH OF MP 3.785	X					
SB	3.667	F	R2-1	24	30																		SPEED LIMIT 40						
SIGN SUMMARY SHEET							SHEET TOTALS	38.75	0.00	0	1	1	7	0	0	8	106.50 120.00							PROJECT NAME: READING-WOODSTOCK					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT							PROJECT NUMBER: STPG SIGN (38)					
										2	3	3	71	0	0	66	990.00						FILE NAME: WOODSTOCK VT-106 SB	PLOT DATE: 4/7/2011					
																							PROJECT MANAGER: A. GAMBLE	DRAWN BY: M. MILLER					
																							DESIGNED BY: M. MILLER	CHECKED BY: A. GAMBLE					
																							WOODSTOCK VT-106 SOUTHBOUND 2	SHEET 40 OF 49					