










DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)				(LB / FT)								
WOODSTOCK SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS							
		A	VD-701	6	8		 BRIDGE / 24 / VT 106			1	1												THE BRIDGE NUMBER PLAQUE TO BE SALVAGED						
		F	OM-3R	12	36			3.00						1	11.0'	X							INSTALL AT 4 FT VERTICAL CLEARANCE MEASURED FROM EDGE OF ROAD TO BOTTOM OF SIGN	X					
		A	VD-701	6	8		BRIDGE / 24 / VT 106				1												SALVAGE THE BRIDGE PLAQUE TO UNDER THE NEW OBJECT MARKER						
SB	3.009	E	OM-3L	12	36		 LEFT OBJECT MARKER					1		X									FACES NB TRAFFIC						
		E	OM-3L	12	36			3.00						1	11.0'	X							INSTALL AT 4 FT VERTICAL CLEARANCE MEASURED FROM EDGE OF ROAD TO BOTTOM OF SIGN	X					
SB	2.871	F	W1-8L	18	24		CHEVRON LEFT					1		X									FACES SB TRAFFIC						
		E	W1-8R	18	24		CHEVRON RIGHT					1		X									FACES NB TRAFFIC						
		F	W1-8L	18	24	FY		3.00						1	12.5'	X							FACES SB; (NEW SIGNS HAVE FLUOR YELLOW SHEETING)	X					
		E	W1-8R	18	24	FY		3.00						1	12.5'	X								FACES NB; INSTALL ON ITS OWN POST DIRECTLY BEHIND THE SB FACING SIGN (FY SHEETING)	X				
SB	2.850	F	VW-133	30	30		HIDDEN DRIVE LEFT					1		X									TO BE REPLACED 165 FT ± SOUTH AT MP 2.819						
SB	2.840	F	W1-8L	18	24		CHEVRON LEFT					1		X									FACES SB TRAFFIC						
		E	W1-8R	18	24		CHEVRON RIGHT					1		X									FACES NB TRAFFIC						
		F	W1-8L	18	24	FY		3.00						1	12.5'	X							FACES SB; (NEW SIGNS HAVE FLUOR YELLOW SHEETING)	X					
		E	W1-8R	18	24	FY		3.00						1	12.25'	X								FACES NB; INSTALL ON ITS OWN POST DIRECTLY BEHIND THE SB FACING SIGN (FY SHEETING)	X				
SB	2.819	F	VW-133	30	30			6.25							1	14.25'	X						INSTALL 110 FT ± SOUTH OF CHEVRONS AT MP 2.840			E-154			
SIGN SUMMARY SHEET							SHEET TOTALS	24.25	0.00	0	1	1	7	0	0	7	86.0							PROJECT NAME: READING-WOODSTOCK					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	FT							PROJECT NUMBER: STPG SIGN (38)				
							338.50	0.00	2	3	3	71	0	0	66	990.00							FILE NAME: WOODSTOCK VT-106 SB	PLOT DATE: 4/7/2011					
																							PROJECT MANAGER: A. GAMBLE	DRAWN BY: M. MILLER					
																							DESIGNED BY: M. MILLER	CHECKED BY: A. GAMBLE					
																							WOODSTOCK VT-106 SOUTHBOUND 4	SHEET 42 OF 49					