

DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)				(LB / FT)								
WOODSTOCK SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS							
SB	2.808	F	W1-8L	18	24		CHEVRON LEFT					1		X								FACES SB TRAFFIC							
		E	W1-8R	18	24		CHEVRON RIGHT					1		X								FACES NB TRAFFIC							
		F	W1-8L	18	24	FY		3.00								1	12.5'	X				FACES SB; (NEW SIGNS HAVE FLUOR YELLOW SHEETING)	X						
		E	W1-8R	18	24	FY		3.00								1	12.25'	X				FACES NB; INSTALL ON ITS OWN POST DIRECTLY BEHIND THE SB FACING SIGN (FY SHEETING)	X						
SB	2.777	F	W1-8L	18	24		CHEVRON LEFT					1		X								THIS SB-FACING CHEVRON WILL NOT BE REPLACED							
		E	W1-8R	18	24		CHEVRON RIGHT					1		X								FACES NB TRAFFIC							
		E	W1-8R	18	24	FY		3.00								1	13.0'	X				FACES NB (FY SHEETING)	X						
SB	2.753	F	W3-5	36	36		SPEED REDUCTION 30-MPH					1		X								TO BE REPLACED FURTHER AHEAD AT MP 2.703							
SB	2.753 2.703	F	W3-5	36	36			9.00								2	14.25'	15.75'	X	INSTALLED AT REMOVAL SITE ABOVE. MUCH BETTER VISIBILITY.			X						
SB	2.684	F	VW-054	30	30		HIDDEN DRIVE RIGHT					1		X															
SB	2.638	F	R2-1	24	30							1		X															
		F	R2-1	30	36			7.50								1	13.5'	X				THE NEW SIGN IS LARGER		6					
SB	2.629	F	VW-060	30	30			6.25								1	13.5'	X				INSTALL BEHIND RAIL 50 FT± SOUTH OF THE SPEED LIMIT 30 SIGN AT MP 2.638; MINOR BRUSH CUT LIKELY REQUIRED			E-154				
SB	2.489	F	R2-1	24	30							1		X															
		F	R2-1	24	30			5.00								1	13.5'	X				BEHIND RAIL	X						
SIGN SUMMARY SHEET							SHEET TOTALS	36.75	0.00	0	0	0	8	0	0	8	108.25							PROJECT NAME: READING-WOODSTOCK					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT							PROJECT NUMBER: STPG SIGN (38)					
							338.50	0.00	2	3	3	71	0	0	66	990.00							FILE NAME: WOODSTOCK VT-106 SB	PLOT DATE: 4/7/2011					
																							PROJECT MANAGER: A. GAMBLE	DRAWN BY: M. MILLER					
																							DESIGNED BY: M. MILLER	CHECKED BY: A. GAMBLE					
																							WOODSTOCK VT-106 SOUTHBOUND 5	SHEET 43 OF 49					