DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WOODSTOCK SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	M1-5	30	24		VERMONT 106						1															
		F	M3-3	24	12			2.00								1		12.0' X								**GREEN ON WHITE**	X		
		F	M1-5	30	24			5.00																				E-136B
SB	2.331	F	R2-1	24	30								1		X													
		F	R2-1	24	30			5.00								1		12.5' X									X		
SB	2.117	F	R2-1	24	30								1		X													
		F	R2-1	24	30			5.00								1		13.0' X									X		
SB	2.080	F	W11-7	30	30		HORSE WITH RIDER (SYMBOL)						1		X											TO BE REPLACED FURTHER AHEAD AT MP 2.016			
		F	W7-3A	24	18		NEXT 2 MILES (PLAQUE)						1															
SB	1.976 ~~2.016~~	F	W11-7	30	30			6.25								1		12.75' X								INSTALL ~~340~~ 210 FT± SOUTH OF THE PREVIOUS POSITION AT MP 2.080	X		
		F	W7-3A	24	18			3.00																			X		
SB	1.938	G	VR-017	24	30								1		X											TOWN FARM RD (TH-58)			
		G	VR-017	24	30			5.00								1		12.5' X								RETAIN TOWN INSTALLED "DEAD END" SIGN (ON SEPARATE POST)		6	
SB	1.934	H	R1-1	30	30		TOWN FARM RD TH58 - 2 EA 1060 1424 0197			2	2	~~1~~ 3			X						STREET SIGN AND MM SALVAGED ON TO THE NEW POST.					TOWN FARM RD (TH-58)			
		H	R1-1	30	30			6.25		1	1	1				1		13.5' X									X		
SIGN SUMMARY SHEET VERMONT AGENCY OF TRANSPORTATION							SHEET TOTALS	37.50 SF	0.00 SF	0 EA	~~0~~ 3 EA	~~0~~ 3 EA	~~7~~ 10 EA	0 EA	0 EA	6 EA	~~90.00~~ 76.25 FT											
							TOWN DIRECTIONAL TOTALS	338.50	0.00	2	3	3	71	0	0	66	990.00											

PROJECT NAME: READING-WOODSTOCK
PROJECT NUMBER: STPG SIGN (38)

FILE NAME: WOODSTOCK VT-106 SB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
WOODSTOCK VT-106 SOUTHBOUND 7

PLOT DATE: 4/7/2011
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE
SHEET 45 OF 49