

# QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE NO. 13	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									141		141		SY	GRUBBING MATERIAL	651.40	1			<b>SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)</b>
								1			1		LS	EPSC PLAN	652.10	-	245	TON	TYPE IIS (VT 114)
								70			70		HR	MONITORING EPSC PLAN	652.20	6	260	TON	TYPE IIS (VT 114)
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-	30	TON	TYPE IIS (TH 52)
								50			50		SY	TEMPORARY EROSION MATTING	653.20	2	535	TON	SUBTOTAL
								3			3		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-	5	TON	ROUNDING
								1			1		EACH	FILTER BAG	653.45	-	540	TON	TOTAL
								625			625		LF	PROJECT DEMARCATION FENCE	653.55	19			
							10				10		EACH	TRANSPLANTING SHRUBS	656.50	-			
							10				10		CY	LANDSCAPE BACKFILL, TRUCK MEASUREMENT	656.80	3.3			
							25				25		SF	TRAFFIC SIGNS, TYPE A	675.20	0.66			
							98				98		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
							15				15		EACH	REMOVING SIGNS	675.50	-			
							6				6		EACH	ERECTING SALVAGED SIGNS	675.60	-			
							3				3		EACH	SETTING SALVAGED POSTS	675.61	-			
							3				3		EACH	DELINEATOR WITH STEEL POST	676.10	-			
							8				8		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-			
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
								65			65		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET) (FPQ)	900.608	2.6			
								110			110		LF	SPECIAL PROVISION (BRIDGE RAILING, TEXAS)	900.640	2.1			
								330			330		LF	SPECIAL PROVISION (PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES)	900.640	-			
								230			230		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NEXT D BEAMS) (NEXT 28 D)	900.640	-			
								1			1		LS	SPECIAL PROVISION (CONSTRUCTION VIBRATION AND CRACK MONITORING)	900.645	-			
							1				1		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645	-			
							1				1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645	-			
										1	1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE) (N.A.B.I.)	900.650	-			
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650	-			
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-			
							230				230		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	5.5			
							540				540		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	5			

CLD 12-0121 MODEL QUANTITY SUMMARY 3



PROJECT NAME: BURKE  
 PROJECT NUMBER: BRF 0269(13)  
 FILE NAME: I0c412/cos/z10c412frm.dgn PLOT DATE: 10/14/2014  
 PROJECT LEADER: J. BYATT DRAWN BY: M. HALEY  
 DESIGNED BY: M. HALEY CHECKED BY: P. SHEDD  
 QUANTITY SHEET 3 SHEET 11 OF 73