

COMPOSITE QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ER STP 0162(19) (BRIDGE 13)	BRF 0162(16) (BRIDGE 15)	BRF 0162(17) (BRIDGE 16)	ER BRF 0162(18) (BRIDGE 19)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							0.25	0.25	0.25	0.25	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
							0.25	0.25	0.25	0.25	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
							750	750	750	750	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							0.25	0.25	0.25	0.25	1		LS	MOBILIZATION/DEMobilIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL (BRF 0162(16))	641.10				
									1		1		LS	TRAFFIC CONTROL (BRF 0162(17))	641.10				
							0.34	0.33	0.33		1		LS	TRAFFIC CONTROL (DETOUR)	641.10				
										1	1		LS	TRAFFIC CONTROL (ER BRF 0162(18))	641.10				
							1				1		LS	TRAFFIC CONTROL (ER STP 0162(19))	641.10				
							4	4	4	7	19		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							910		710	1300	2920		LF	4 INCH WHITE LINE	646.20				
							910		710	1225	2845		LF	4 INCH YELLOW LINE	646.21				
										20	20		LF	24 INCH STOP BAR	646.26				
										4	4		EACH	LETTER OR SYMBOL	646.30				
								780			780		LF	DURABLE 4 INCH WHITE LINE, RECESSED THERMOPLASTIC	646.408				
								900			900		LF	DURABLE 4 INCH YELLOW LINE, RECESSED THERMOPLASTIC	646.418				
								45			45		LF	DURABLE 24 INCH STOP BAR, TYPE I TAPE	646.481				
								10			10		EACH	DURABLE LETTER OR SYMBOL, TYPE I TAPE	646.491				
										1800	1800		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
										1000	1000		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
										35	35		LF	TEMPORARY 24 INCH STOP BAR	646.680				
							1320	625	750	1725	4420		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							300	275	430	470	1475		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								240	225	570	1035		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							6	6	10	20	42		LB	SEED	651.15				
							55	45	100	160	360		LB	FERTILIZER	651.18				
							0.25	0.2	1	0.75	2.2		TON	AGRICULTURAL LIMESTONE	651.20				
							0.25	0.2	1	0.75	2.2		TON	HAY MULCH	651.25				
							30	35	38	90	193		CY	TOPSOIL	651.35				
							170	160	260	810	1400		SY	GRUBBING MATERIAL	651.40				
							1				1		LS	EPSC PLAN (BRIDGE 13)	652.10				
								1			1		LS	EPSC PLAN (BRIDGE 15)	652.10				
									1		1		LS	EPSC PLAN (BRIDGE 16)	652.10				
										1	1		LS	EPSC PLAN (BRIDGE 19)	652.10				
							80	80	80	80	320		HR	MONITORING EPSC PLAN	652.20				
							1	1	1	1	4		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							130	25	240	500	895		SY	TEMPORARY EROSION MATTING	653.20				
								25			25		SY	PERMANENT EROSION MATTING	653.21				
							40	1	8		49		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
							30	30	30	30	120		CY	VEHICLE TRACKING PAD	653.35				



PROJECT NAME: ROCHESTER
 PROJECT NUMBER: 0162(19), 0162(16), 0162(17), 0162(18)
 FILE NAME: z11c332combined_qs.dgn PLOT DATE: 09/16/2013
 PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA
 DESIGNED BY: E.A. FIALA CHECKED BY: G.S. GOODRICH
COMPOSITE QUANTITY SHEET #3 SHEET 6 OF 238