

COMPOSITE QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ER STP 0162(19) (BRIDGE 13)	BRF 0162(16) (BRIDGE 15)	BRF 0162(17) (BRIDGE 16)	ER BRF 0162(18) (BRIDGE 19)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1			1		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
						1			1	2		EACH	FILTER BAG	653.45				
							630	380	485	1495		LF	BARRIER FENCE	653.50				
						495	210	300	900	1905		LF	PROJECT DEMARCATION FENCE	653.55				
						1	29	1	28	59		SF	TRAFFIC SIGNS, TYPE A	675.20				
						30	90	30	150	300		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							10	5	12	27		EACH	REMOVING SIGNS	675.50				
								1	7	8		EACH	ERECTING SALVAGED SIGNS	675.60				
									1	1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40				
						1			1	2		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
									29	29		CY	SPECIAL PROVISION (COMPRESSIBLE FILL)	900.608				
							17	15		32		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				
						750				750		CY	SPECIAL PROVISION (STONE FILL, CHANNEL FLOWLINE)	900.608				
						4				4		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION TO CONCRETE MEDIAN BARRIER)	900.620				
							4			4		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM)(COATED BLACK)	900.620				
								1		1		EACH	SPECIAL PROVISION (ROCK ANCHOR TESTING)	900.620				
							120			120		LF	SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED STEEL TUBING)(COATED BLACK)	900.640				
							71			71		LF	SPECIAL PROVISION (GUARDRAIL TRANSITION, STEEL BEAM TO BOX BEAM)(COATED BLACK)	900.640				
								116		116		LF	SPECIAL PROVISION (PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES, ROCK)	900.640				
							141			141		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NEXT D BEAMS)(NEXT 28 D)(FASCIA)	900.640				
							141	197		338		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NEXT D BEAMS)(NEXT 28 D)	900.640				
								53		53		LF	SPECIAL PROVISION (ROCK ANCHOR)	900.640				
						0.25	0.25	0.25	0.25	1		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645				
									1	1		LS	SPECIAL PROVISION (REMOVAL OF TEMPORARY BRIDGE)	900.645				
						1				1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645				
						1				1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)(BRIDGE 13)	900.650				
							1			1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)(BRIDGE 15)	900.650				
								1		1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)(BRIDGE 16)	900.650				
						1	1	1	1	4		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
						1	1	1	1	4		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
							105	17		122		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675				
						415	465	295	580	1755		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: ROCHESTER
 PROJECT NUMBER: 0162(19), 0162(16), 0162(17), 0162(18)
 FILE NAME: z11c332combined_qs.dgn PLOT DATE: 09/16/2013
 PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA
 DESIGNED BY: E.A. FIALA CHECKED BY: G.S. GOODRICH
COMPOSITE QUANTITY SHEET #4 SHEET 7 OF 238

