

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEM	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							40				40		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							120				120		HR	FLAGGERS	630.15				
										0.25	0.25		LS	FIELD OFFICE, ENGINEERS	631.10				
										0.25	0.25		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										0.25	0.25		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										750	750		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							0.25				0.25		LS	MOBILIZATION/DEMobilIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL (ER BRF 0162(18))	641.10				
							7				7		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							1300				1300		LF	4 INCH WHITE LINE	646.20				
							1225				1225		LF	4 INCH YELLOW LINE	646.21				
							20				20		LF	24 INCH STOP BAR	646.26				
							4				4		EACH	LETTER OR SYMBOL	646.30				
							1800				1800		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
							1000				1000		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
							35				35		LF	TEMPORARY 24 INCH STOP BAR	646.680				
								1650			1650		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								470			470		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WMRE REINFORCED	649.515				
								570			570		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								20			20		LB	SEED	651.15				
								160			160		LB	FERTILIZER	651.18				
								0.75			0.75		TON	AGRICULTURAL LIMESTONE	651.20				
								0.75			0.75		TON	HAY MULCH	651.25				
								90			90		CY	TOPSOIL	651.35				
								810			810		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN (BRIDGE 19)	652.10				
								80			80		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								500			500		SY	TEMPORARY EROSION MATTING	653.20				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								1			1		EACH	FILTER BAG	653.45				
								485			485		LF	BARRIER FENCE	653.50				
								900			900		LF	PROJECT DEMARCATION FENCE	653.55				
								28			28		SF	TRAFFIC SIGNS, TYPE A	675.20				
								150			150		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
								12			12		EACH	REMOVING SIGNS	675.50				
								7			7		EACH	ERECTING SALVAGED SIGNS	675.60				
								1			1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40				
								1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
									29		29		CY	SPECIAL PROVISION (COMPRESSIBLE FILL)	900.608				

PROJECT NAME: ROCHESTER
 PROJECT NUMBER: ER BRF 0162(18)
 FILE NAME: z10c332qs.dgn PLOT DATE: 08/12/2013
 PROJECT LEADER: S.E. BURBANK DRAWN BY: E.A. FIALA
 DESIGNED BY: J.J. WESTCOTT CHECKED BY: S.E. BURBANK
 QUANTITY SHEET #2 SHEET 183 OF 238

