

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE NO. C65B	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			
							1050		115		1165		CY	COMMON EXCAVATION	203.15	8			
							290				290		CY	SOLID ROCK EXCAVATION	203.16	4			
									165		165		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	3.4			
							10				10		CY	EARTH BORROW	203.30	-			
							450				450		CY	SAND BORROW	203.31	2			
									110		110		CY	GRANULAR BORROW	203.32	3.2			
							110				110		CY	TRENCH EXCAVATION OF EARTH	204.20	3.9			
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
									790		790		CY	STRUCTURE EXCAVATION	204.25	4.7			
							15		610		625		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	2.1			
							1100				1100		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	10			
							980				980		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	6			
							8				8		CWT	EMULSIFIED ASPHALT	404.65	0.3			
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
									1		1		LS	PRECAST CONCRETE STRUCTURE (7'-0" X 5'-0" X 62'-0" BOX CULVERT)	540.10	-			
							164				164		LF	18" CPEP	601.0915	-			
							2				2		EACH	18" CPEPES	601.7015	-			
							80				80		HR	BULLDOZER RENTAL, TYPE I	608.10	EST.			
							80				80		HR	POWER GRADER RENTAL	608.15	EST.			
							80				80		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
							5				5		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
							80				80		HR	TRUCK RENTAL	608.37	EST.			
							80				80		HR	LOADER RENTAL, TYPE I	608.40	EST.			
								100			100		CY	STONE FILL, TYPE II	613.11	2.4			
								150			150		CY	STONE FILL, TYPE III	613.12	4.7			
							14				14		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	0.1			
							2				2		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-			
							2				2		EACH	YIELDING MARKER POSTS	619.17	-			
							410				410		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	2			
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
							275				275		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
							200				200		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							200				200		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1				1		LS	TRAFFIC CONTROL	641.10	-			

PROJECT NAME: BARRE TOWN
 PROJECT NUMBER: STP SCR(10)
 FILE NAME: z10d202qss.dgn PLOT DATE: 2/27/2014
 PROJECT LEADER: K. UPMAL DRAWN BY: W. GORDON
 DESIGNED BY: P. SHEDD CHECKED BY: P. SHEDD
 QUANTITY SHEET I SHEET II OF 43