

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE NO. C65B	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)
							2				2		EACH	PORTABLE ARROW BOARD	641.16	-	160	TON	TYPE IVS WEARING COURSE
							1100				1100		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	-	23	TON	TYPE IVS LEVELING COURSE
							1100				1100		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	-	194	TON	TYPE I IS INTERMEDIATE COURSE
							50				50		EACH	LINE STRIPING TARGETS	646.76	EST.	168	TON	TYPE I IS BASE COURSE
								370			370		SY	GEOTEXTILE UNDER STONE FILL	649.31	2.9	545	TON	PROJECT SUBTOTAL
								20			20		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	1	5	TON	ROUNDING
								50			50		LB	SEED	651.15	6	550	TON	PROJECT TOTAL
								275			275		LB	FERTILIZER	651.18	-			
								1.5			1.5		TON	AGRICULTURAL LIMESTONE	651.20	0.4			
								1.5			1.5		TON	HAY MULCH	651.25	0.4			
							260				260		CY	TOPSOIL	651.35	3			
									110		110		SY	GRUBBING MATERIAL	651.40	1.8			
								1			1		LS	EPSC PLAN	652.10	-			
								80			80		HR	MONITORING EPSC PLAN	652.20	EST.			
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
								785			785		SY	TEMPORARY EROSION MATTING	653.20	3			
								1			1		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	EST.			
								15			15		CY	VEHICLE TRACKING PAD	653.35	-			
								3			3		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-			
								450			450		LF	BARRIER FENCE	653.50	8			
								570			570		LF	PROJECT DEMARCATION FENCE	653.55	7			
							1				1		LS	TREE PROTECTION	656.85	-			
							1				1		SF	TRAFFIC SIGNS, TYPE A	675.20	0.2			
							35				35		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
							1				1		EACH	REMOVING SIGNS	675.50	-			
							1				1		EACH	ERECTING SALVAGED SIGNS	675.60	-			
							4				4		EACH	DELINEATOR WITH STEEL POST	676.10	-			
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
									1		1		LS	SPECIAL PROVISION (REMOVE AND RESET EXISTING STONE WALL)	900.645	-			
									1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645	-			
							1				1		LS	SPECIAL PROVISION (TEMPORARY ROADWAY)	900.645	-			
									1		1		LS	SPECIAL PROVISION (TEMPORARY STEEL SHEET PILING)	900.645	-			
							1				1		LS	SPECIAL PROVISION (TEMPORARY SUPPORT OF WATER MAIN)	900.645	-			
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650	-			
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-			
							560				560		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	-			
							550				550		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	5			

PROJECT NAME: BARRE TOWN  
 PROJECT NUMBER: STP SCR(10)  
 FILE NAME: z10d202qss.dgn PLOT DATE: 2/27/2014  
 PROJECT LEADER: K. UPMAL DRAWN BY: W. GORDON  
 DESIGNED BY: P. SHEDD CHECKED BY: P. SHEDD  
 QUANTITY SHEET 2 SHEET 12 OF 43