

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
					ROADWAY	EROSION CONTROL	UTILITIES	BRIDGE	FULL C.E.	WATERLINE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
														END OPTION DD						
					225						225		LF	18" CPEP(SL)	601.2615					
					3						3		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18					
					2						2		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40					
					1						1		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42					
					10						10		MGAL	DUST CONTROL WITH WATER	609.10					
						250					250		CY	STONE FILL, TYPE III	613.12					
					460						460		LF	VERTICAL GRANITE CURB	616.21					
					25						25		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28					
					510						510		LF	REMOVAL OF EXISTING CURB	616.41					
					245						245		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10					
					35						35		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11					
					40						40		SF	DETECTABLE WARNING SURFACE	618.30					
					73						73		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80					
										2	2		EACH	ADJUST ELEVATION OF VALVE BOX	629.20					
										72	72		LF	DUCTILE IRON PIPE, CEMENT-LINED (8")	629.24					
										3	3		EACH	GATE VALVE WITH VALVE BOX (8")	629.27					
										1	1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM	629.42					
					80						80		HR	UNIFORMED TRAFFIC OFFICERS	630.10					
					500						500		HR	FLAGGERS	630.15					
									1		1		LS	FIELD OFFICE, ENGINEERS	631.10					
									1		1		LS	TESTING EQUIPMENT, CONCRETE	631.16					
									1		1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17					
									3000		3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26					
					1						1		LS	MOBILIZATION/DEMobilIZATION	635.11					
					8						8		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15					
					1115						1115		LF	DURABLE 4 INCH WHITE LINE	646.400					
					1060						1060		LF	DURABLE 4 INCH YELLOW LINE	646.410					
					310						310		LF	DURABLE 12 INCH WHITE LINE	646.460					
					45						45		LF	DURABLE 24 INCH STOP BAR	646.480					
					8						8		EACH	DURABLE LETTER OR SYMBOL	646.490					
						450					450		SY	GEOTEXTILE UNDER STONE FILL	649.31					
						130					130		SY	GEOTEXTILE FOR SILT FENCE	649.51					
						90					90		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515					
						3					3		LB	SEED	651.15					
						25					25		LB	FERTILIZER	651.18					
						1					1		TON	AGRICULTURAL LIMESTONE	651.20					
						1					1		TON	HAY MULCH	651.25					
						25					25		CY	TOPSOIL	651.35					
						175					175		SY	GRUBBING MATERIAL	651.40					

PROJECT NAME: LUDLOW
 PROJECT NUMBER: BRF 025-1(42)
 FILE NAME: z10j068qs.dgn
 PROJECT LEADER: A.P. GUYETTE
 DESIGNED BY: E.F. LAWES
 QUANTITY SHEET #2

PLOT DATE: 07/21/2016
 DRAWN BY: E.F. LAWES
 CHECKED BY: A.P. GUYETTE
 SHEET 9 OF 72

