QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

				ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				77,000	77,000	LB	BITUMINOUS CRACK SEALING (AASHTO M 324 (ASTM D 6690) TYPE IV)	417.10	605
				27,000	27,000	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	291
				1,600	1,600	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
				2,800	2,800	HR	FLAGGERS	630.15	EST
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST
				1	1	LS	TRAFFIC CONTROL	641.10	EST
				2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		BITUMINOUS CRACK SEALING (AASHTO M 324 (ASTM D 6690) TYPE IV)
3,699	LB	I-89 SB SO. BURLINGTON - COLCHESTER
7,110	LB	I-89 SB ROYALTON - BETHEL
1,980	LB	I-89 SB RANDOLPH
5,850	LB	I-89 NB ROYALTON - BETHEL
5,040	LB	I-89 NB COLCHESTER - MILTON
14,800	LB	VT 14 HARTFORD - ROYALTON
~~205~~	~~LB~~	~~VT 132 SHARON~~ *
3,265	LB	US 7 NEW HAVEN - FERRISBURGH
5,315	LB	US 7 SALISBURY - MIDDLEBURY
4,860	LB	VT 9 WILMINGTON
7,870	LB	VT 103 ROCKINGHAM - CHESTER
~~1,750~~	~~LB~~	~~VT 106 WEATHERSFIELD~~ **
795	LB	US 5 HARTLAND
2,753	LB	US 5 HARTLAND - HARTFORD
1,654	LB	US 5 HARTFORD
1,855	LB	VT 214 PLAINFIELD - EAST MONTPELIER
842	LB	VT 4A FAIR HAVEN
3,191	LB	VT 4A FAIR HAVEN - CASTLETON
~~529~~	~~LB~~	~~FAIR HAVEN STATE HIGHWAY~~ ***
184	LB	US 4 EB FAIR HAVEN
549	LB	US 4 WB FAIR HAVEN
2,299	LB	INTERSTATE RAMPS
605	LB	ROUNDING
77,000	LB	TOTAL
		BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)
4,710	LB	I-91 SB SHEFFIELD - BARTON
9,927	LB	I-91 SB ROCKINGHAM - SPRINGFIELD
10,909	LB	I-89 SB ST. ALBANS - HIGHGATE
1,163	LB	INTERSTATE RAMPS
291	LB	ROUNDING
27,000	LB	TOTAL
529	LB	FAIR HAVEN STATE HIGHWAY
*		ELIMINATED VIA WO#01
**		ELIMINATED VIA WO#04
***		CHANGED TO "BLOW AND GO" ONLY

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: STATEWIDE

PROJECT NUMBER: STP CRAK(29)

FILE NAME: p10k430.dgn
PROJECT LEADER: FOWLER
DESIGNED BY: LOCKE
p10k430qs.i

PLOT DATE: 10-OCT-2012 11:30
DRAWN BY: LOCKE
CHECKED BY: PAVT MGMT
SHEET 3 OF 12