

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES						
					ROADWAY	EROSION CONTROL	BRIDGE NO. 2	BRIDGE NO. 5	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					160					160		LB	FERTILIZER	651.18				
					2					2		TON	AGRICULTURAL LIMESTONE	651.20				
					2					2		TON	HAY MULCH	651.25				
					120					120		CY	TOPSOIL	651.35				
					985					985		SY	GRUBBING MATERIAL	651.40				
						1				1		LS	EPSC PLAN (VT 125 - BRIDGE NO. 2)	652.10				
						1				1		LS	EPSC PLAN (VT 125 - BRIDGE NO. 5)	652.10				
						80				80		HR	MONITORING EPSC PLAN	652.20				
						1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (VT 125 - BRIDGE NO. 2)	652.30				
						1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (VT 125 - BRIDGE NO. 5)	652.30				
					1850					1850		SY	TEMPORARY EROSION MATTING	653.20				
					10					10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
					60					60		CY	VEHICLE TRACKING PAD	653.35				
					2					2		EACH	FILTER BAG	653.45				
					1450					1450		LF	PROJECT DEMARCATION FENCE	653.55				
					1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
							160	90		250		CY	SPECIAL PROVISION (STONE FILL, CULVERT LINING)	900.608				
								225		225		LF	SPECIAL PROVISION (WLDLIFE GUIDE FENCE)	900.640				
							1			1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM) (VT 125 - BRIDGE NO. 2)	900.645				
								1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM) (VT 125 - BRIDGE NO. 5)	900.645				
					1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (VT 125 - BRIDGE NO. 2)	900.645				
					1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (VT 125 - BRIDGE NO. 5)	900.645				
							1			1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)(VT 125 - BRIDGE NO. 2)	900.650				
								1		1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)(VT 125 - BRIDGE NO. 5)	900.650				
						1	1			2		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
						1	1			2		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
							470	340		810		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

NOTE: FOR DETAILED BREAKDOWN OF QUANTITIES BETWEEN BR2 AND BR5 SEE BR2 AND BR5 QUANTITY SHEETS

PROJECT NAME: BRIDPORT  
PROJECT NUMBER: STP CULV(29)

FILE NAME: zllc264frm.dgn  
PROJECT LEADER: M. CHENETTE  
DESIGNED BY: J. HUNGERFORD  
QUANTITY SHEET 2

PLOT DATE: 9/12/2014  
DRAWN BY: L. BUXTON  
CHECKED BY: J. HUNGERFORD  
SHEET 6 OF 57

