

## BR2 QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE NO. 2	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						780				780		CY	COMMON EXCAVATION	203.15				
								400		400		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
						0.5				0.5		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								1900		1900		CY	STRUCTURE EXCAVATION	204.25				
								1100		1100		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
						340				340		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
						570				570		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
								5		5		GAL	WATER REPELLENT, SILANE	514.10				
								200		200		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
								1		1		EACH	REMOVAL OF STRUCTURE (16' X 11' x 68' CMPPA)	529.15				
								1		1		LS	PRECAST CONCRETE STRUCTURE (20'-0" X 10'-0" X 66'-0" BOX)	540.10				
						0.5				0.5		MGAL	DUST CONTROL WITH WATER	609.10				
						0.5				0.5		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
								700		700		CY	STONE FILL, TYPE II	613.11				
						67				67		LF	REMOVAL OF EXISTING FENCE	620.55				
						650				650		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205				
						4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						538				538		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						100				100		HR	FLAGGERS	630.15				
									0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
									0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						0.5				0.5		LS	MOBILIZATION/DEMobilIZATION	635.11				
						7				7		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						680				680		LF	DURABLE 4 INCH WHITE LINE	646.400				
						680				680		LF	DURABLE 4 INCH YELLOWLINE	646.410				
						525				525		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
								1050		1050		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							60			60		SY	GEOTEXTILE FOR SILT FENCE	649.51				
						20				20		LB	SEED	651.15				
						90				90		LB	FERTILIZER	651.18				
						1				1		TON	AGRICULTURAL LIMESTONE	651.20				
						1				1		TON	HAY MULCH	651.25				
						70				70		CY	TOPSOIL	651.35				
						950				950		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN	652.10				
							40			40		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							1500			1500		SY	TEMPORARY EROSION MATTING	653.20				

PROJECT NAME: BRIDPORT  
 PROJECT NUMBER: STP CULV(29)

FILE NAME: zllc264frm.dgn  
 PROJECT LEADER: M. CHENETTE  
 DESIGNED BY: J. HUNGERFORD  
 BR2 QUANTITY SHEET 1

PLOT DATE: 8/22/2014  
 DRAWN BY: L. BUXTON  
 CHECKED BY: J. HUNGERFORD  
 SHEET 7 OF 57

