

BR5 QUANTITY SHEET I

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAYS	EROSION CONTROL	BRIDGE NO. 5	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							550				550		CY	COMMON EXCAVATION	203.15				
									140		140		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							0.5				0.5		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									570		570		CY	STRUCTURE EXCAVATION	204.25				
									330		330		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
							320				320		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
							400				400		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
									2		2		GAL	WATER REPELLENT, SILANE	514.10				
									100		100		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
									1		1		EACH	REMOVAL OF STRUCTURE (84" X 41'-0" CGMP)	529.15				
									1		1		LS	PRECAST CONCRETE STRUCTURE (12'-0" X 9'-0" X 41'-0" BOX)	540.10				
							0.5				0.5		MGAL	DUST CONTROL WITH WATER	609.10				
							0.5				0.5		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
							115				115		CY	STONE FILL, TYPE I	613.10				
									30		30		CY	STONE FILL, TYPE II	613.11				
							1				1		EACH	RELOCATE MAILBOX, MULTIPLE SUPPORT	617.12				
							463				463		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
							188				188		LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.206				
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							363				363		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							100				100		HR	FLAGGERS	630.15				
										0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
										0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							0.5				0.5		LS	MOBILIZATION/DEMOLITION	635.11				
							6				6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							560				560		LF	DURABLE 4 INCH WHITE LINE	646.400				
							560				560		LF	DURABLE 4 INCH YELLOW LINE	646.410				
							250				250		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
									40		40		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								40			40		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							10				10		LB	SEED	651.15				
							70				70		LB	FERTILIZER	651.18				
							1				1		TON	AGRICULTURAL LIMESTONE	651.20				
							1				1		TON	HAY MULCH	651.25				
							50				50		CY	TOPSOIL	651.35				
							35				35		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								40			40		HR	MONITORING EPSC PLAN	652.20				

PROJECT NAME: BRIDPORT
 PROJECT NUMBER: STP CULV(29)

FILE NAME: zllc264frm.dgn
 PROJECT LEADER: M. CHENETTE
 DESIGNED BY: J. HUNGERFORD
 BR5 QUANTITY SHEET I

PLOT DATE: 8/22/2014
 DRAWN BY: L. BUXTON
 CHECKED BY: J. HUNGERFORD
 SHEET 9 OF 57

