QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		TRAINING	FULL CE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				6	6	TON	AGRICULTURAL LIMESTONE	651.20	EST.
				5	5	TON	HAY MULCH	651.25	EST.
				250	250	CY	TOPSOIL	651.35	21.2
				23500	23500	SY	GRUBBING MATERIAL (2")	651.40	223
				25	25	SY	GRUBBING MATERIAL (6")	651.40	4.1
				7900	7900	SY	TEMPORARY EROSION MATTING	653.20	101.9
				3100	3100	LF	BARRIER FENCE	653.50	4
				3100	3100	LF	EROSION LOG	653.60	4
				510	510	SF	TRAFFIC SIGNS, TYPE A	675.20	12.72
				1704	1704	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-
				135	135	EA	REMOVING SIGNS	675.50	-
				6	6	EA	ERECTING SALVAGED SIGNS	675.60	-
				22	22	EA	DELINEATOR WITH STEEL POST	676.10	-
				25	25	EA	REMOVAL OF EXISTING DELINEATOR	676.12	-
				1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
				4	4	EA	SPECIAL PROVISION (CORING CONCRETE)	900.620	-
				5	5	EA	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-
				1	1	EA	SPECIAL PROVISION (DECOMMISSION CURB DROP INLET)	900.620	-
				1	1	EA	SPECIAL PROVISION (GNSS CONSTRUCTION INSPECTION EQUIPMENT)	900.620	-
				528	528	LF	SPECIAL PROVISION (BARRIER FOR TEMPORARY TRAFFIC PROTECTION)	900.640	-
				1	1	LS	SPECIAL PROVISION (GPS MACHINE CONTROL GRADING)	900.645	-
				125000	125000	SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	1580
				1650	1650	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	77.4
				125000	125000	SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	1580
				4500	4500	TON	SPECIAL PROVISION (AGGREGATE TO MEET COLD MIXED GRADATION)	900.680	170
				14000	14000	TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	105.0
				29000	29000	TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)	900.680	135
				1900	1900	TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	38
				290	290	TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	82
				800	800	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	EST.
				1600	1600	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	44.9
				12500	12500	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT, COLD MIX WITH CEMENT)	900.683	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		TEMPORARY EROSION MATTING
50.1	SY	ITEM DETAIL SUMMARY SHEET
7748	SY	DITCH CLEANING DETAIL SHEET
101.9	SY	ROUNDING
7900	SY	TOTAL
		SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)
10179	TON	MAINLINE
213.4	TON	SIDE ROADS
3502.6	TON	LEVELING
105.0	TON	ROUNDING
14000	TON	TOTAL
		SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)
28865	TON	COLD MIX
135	TON	ROUNDING
29000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: ELMORE-MORRISTOWN
PROJECT NUMBER: STP 2937 (1)

FILE NAME: z11c310.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: S. LAMPHERE
PLOT FILE: z11c310_16.i

PLOT DATE: 3/3/14
DRAWN BY: S. LAMPHERE
CHECKED BY: C. LATHROP
SHEET 16 OF 194