STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10

MILE MARKER, STATION OR SIGN NUMBER		SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																					REMARKS	SIGN DETAIL	
											NO. OF	FLANGED CHANNEL			SQUARE STEEL (in)					TUBULAR ALUMINUM Ø (IN)				TUBULAR STEEL Ø (IN)				W-SHAPE STEEL							
															1.75	2.00	2.50			3.00	4.00	4.0 MOD		3.00	3.50	4.00	5.00	FTG. SIZE							
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	POST	(LB / FT) 1.12	2.00	3.00	(LB / FT) 1.88	2.42	3.35	ANCHOR	SLEEVE	(LB / FT) 1.30	1.70	1.70	FOUND-ATION	(LB / FT) 7.60	9.00	10.80	14.60	24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
OPTION ITEMS																																			
STA. 369+60 RT ELMORE	0120 0804 0700	1	6	10	0.42						1				8			X															VD-700		E-138
STA. 378+90 RT ELMORE	SPEED LIMIT 50	1	24	30	5.00						1					15		X															R2-1		SHSM
STA. 378+92 LT ELMORE	SPEED LIMIT 35	1	30	36	7.50						1					15		X															R2-1		SHSM
STA. 380+16 LT ELMORE	0120 0804 0720	1	6	10	0.42						1				8			X															VD-700		E-138
STA. 383+00 LT ELMORE	Elmore Worcester 11	1	30	18	3.75						1					15																	VD-018	111	
STA. 385+29 LT ELMORE	SPEED LIMIT 35	1	36	36	9.00						2					30		X															W3-5		SHSM
												FT	FT	FT	FT 16	FT 75	FT		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 26.09	SF	EA.	SF				FT			FT 91					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 10

PROJECT NAME: ELMORE-MORRISTOWN
PROJECT NUMBER: STP 2937 (1)

FILE NAME: z11c310.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: S. LAMPHERE
PLOT FILE: z11c310_99.i

PLOT DATE: 3/3/14
DRAWN BY: S. LAMPHERE
CHECKED BY: C. LATHROP
SHEET 99 OF 194