

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Direction	Maximum Banking	Design Speed
Tangent	POB	185+00.00	727497.3899	1635490.342						
	PC	189+02.70	727864.5168	1635655.827						
Elmore Curve #1	PC	189+02.70	727864.5168	1635655.827	2325	707.48	17°26'04.63"	Left	0.045	50
	PI	192+59.19	728189.5191	1635802.324						
	CC	728619.9483	1633536.21							
	PT	196+10.18	728543.4837	1635844.715						
Tangent	PT	196+10.18	728543.4837	1635844.715						
	PC	208+07.70	729732.5078	1635987.111						
Elmore Curve #2	PC	208+07.70	729732.5078	1635987.111	2900	702.41	13°52'39.47"	Right	0.038	50
	PI	211+60.63	730082.9359	1636029.078						
	CC	729387.6703	1638866.536							
	PT	215+10.11	730413.0693	1636153.87						
Tangent	PT	215+10.11	730413.0693	1636153.87						
	PC	219+17.91	730794.5252	1636298.062						
Elmore Curve #3	PC	219+17.91	730794.5252	1636298.062	5000	162.19	0°11'09.09"	Left	NC	50
	PI	219+99.00	730870.3825	1636326.736						
	CC	748473.8188	1589527.958							
	PT	220+80.10	730946.3324	1636355.164						
Tangent	PT	220+80.10	730946.3324	1636355.164						
	PC	222+36.97	731093.2465	1636410.154						
Elmore Curve #4	PC	222+36.97	731093.2465	1636410.154	10000	125.16	0°43'01.53"	Right	NC	50
	PI	222+99.55	731151.8544	1636432.091						
	CC	727587.7492	1645775.596							
	PT	223+62.12	731210.1832	1636454.76						
Tangent	PT	223+62.12	731210.1832	1636454.76						
	PC	227+82.58	731602.0885	1636607.07						
Elmore Curve #5	PC	227+82.58	731602.0885	1636607.07	14000	358.33	1°27'59.37"	Right	NC	50
	PI	229+61.76	731769.0951	1636671.975						
	CC	726530.681	1649656.239							
	PT	231+40.92	731934.3858	1636741.133						
Tangent	PT	231+40.92	731934.3858	1636741.133						
	PC	236+24.71	732380.6892	1636927.867						
Elmore Curve #6	PC	236+24.71	732380.6892	1636927.867	8500	217.55	1°27'59.24"	Left	NC	50
	PI	237+33.49	732481.0419	1636969.855						
	CC	735661.51	1629086.552							
	PCC	238+42.26	732582.4362	1637009.261						
Elmore Curve #6	PCC	238+42.26	732582.4362	1637009.261	1425	756.15	30°24'10.06"	Left	0.064	50
	PI	242+29.46	732943.34	1637149.522						
	CC	733098.6339	1635681.042							
	PT	245+98.41	733325.5985	1637087.851						
Tangent	PT	245+98.41	733325.5985	1637087.851						
	PC	247+73.54	733498.4935	1637059.957						
Elmore Curve #7	PC	247+73.54	733498.4935	1637059.957	12000	1237.7	5°54'34.53"	Right	NC	50
	PI	253+92.94	734109.9869	1636961.303						
	CC	735409.7744	1648906.771							
	PT	260+11.24	734728.3879	1636926.132						
Tangent	PT	260+11.24	734728.3879	1636926.132						
	PC	263+18.60	735035.252	1636908.68						
Elmore Curve #8	PC	263+18.60	735035.252	1636908.68	4000	119.9	1°43'02.60"	Left	0.029	50
	PI	263+78.55	735095.1079	1636905.276						
	CC	734808.1231	1632915.133							
	PT	264+38.50	735154.835	1636900.079						
Tangent	PT	264+38.50	735154.835	1636900.079						
	PC	265+22.49	735238.5064	1636892.799						
Elmore Curve #9	PC	265+22.49	735238.5064	1636892.799	2075	671.76	18°32'56.40"	Left	0.042	50
	PI	268+61.33	735576.0772	1636863.429						
	CC	735058.6496	1634825.609							
	PCC	271+94.25	735886.7686	1636728.197						

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Direction	Maximum Banking	Design Speed
Elmore Curve #9	PCC	271+94.25	735886.7686	1636728.197	7591.35	230.29	1°44'17.13"	Left	RC / NC	50
	PI	273+09.40	735992.3529	1636682.241						
	CC	732857.11	1629767.611							
	PT	274+24.54	736096.4946	1636633.103						
Tangent	PT	274+24.54	736096.4946	1636633.103						
	PC	279+87.94	736606.0302	1636392.686						
Elmore Curve #10	PC	279+87.94	736606.0302	1636392.686	57000	914.62	0°55'09.71"	Right	NC	50
	PI	284+45.26	737019.6216	1636197.539						
	CC	760929.0978	1687942.549							
	PT	289+02.56	737436.2908	1636009.053						
Tangent	PT	289+02.56	737436.2908	1636009.053						
	PC	290+05.69	737530.2586	1635966.545						
Elmore Curve #11	PC	290+05.69	737530.2586	1635966.545	5800	953.82	9°25'20.55"	Right	0.02	50
	PI	294+83.68	737965.7592	1635769.541						
	CC	739920.7547	1641251.006							
	PT	299+59.51	738427.636	1635646.491						
Tangent	PT	299+59.51	738427.636	1635646.491						
	PC	300+55.30	738520.198	1635621.831						
Elmore Curve #12	PC	300+55.30	738520.198	1635621.831	1625	633.11	22°19'22.41"	Right	0.058	50
	PI	303+75.93	738830.0141	1635539.292						
	CC	738938.5286	1637192.062							
	PT	306+88.42	739147.9626	1635580.614						
Tangent	PT	306+88.42	739147.9626	1635580.614						
	PC	309+74.90	739432.0549	1635617.537						
Elmore Curve #13	PC	309+74.90	739432.0549	1635617.537	3125	586.03	10°44'41.02"	Left	0.037	50
	PI	312+68.78	739723.4827	1635655.412						
	CC	739834.8124	1632518.6							
	PCC	315+60.93	740016.8624	1635638.292						
Elmore Curve #13	PCC	315+60.93	740016.8624	1635638.292	5000	129.44	1°28'59.80"	Left	0.037	50
	PI	316+25.66	740081.4762	1635634.522						
	CC	739725.5825	1630646.784							
	PCC	316+90.37	740145.9708	1635629.08						
Elmore Curve #13	PCC	316+90.37	740145.9708	1635629.08	3000	101.51	1°56'19.08"	Left	0.037	50
	PI	317+41.13	740196.5492	1635624.812						
	CC	739893.7378	1632639.702							
	PCC	317+91.88	740246.9543	1635618.836						
Elmore Curve #13	PCC	317+91.88	740246.9543	1635618.836	6250	569.67	5°13'20.37"	Left	0.02	50
	PI	320+76.91	740530.0028	1635585.277						
	CC	739511.0865	1629412.307							
	PCC	323+61.55	740808.8218	1635526.094						
Elmore Curve #13	PCC	323+61.55	740808.8218	1635526.094	3600	544.31	8°39'46.43"	Left	0.032	50
	PI	326+34.22	741075.5517	1635469.477						
	CC	740061.3263	1632004.553							
	PT	329+05.85	741330.711	1635373.33						
Tangent	PT	329+05.85	741330.711	1635373.33						
	PC	331+35.78	741545.6965	1635291.807						
Elmore Curve #14	PC	331+35.78	741545.6965	1635291.807	25000	255.4	0°35'07.18"	Right	NC	50
	PI	332+63.48	741665.0999	1635246.528						
	CC	750409.9103	1658667.557							
	PT	333+91.17	741784.9596	1635202.472						
Tangent	PT	333+91.17	741784.9596	1635202.472						
	PC	336+78.65	742054.7886	1635103.292						
Elmore Curve #15	PC	336+78.65	742054.7886	1635103.292	6000	412.68	3°56'26.75"	Right	0.02	50
	PI	338+85.07	742248.5344	1635032.078						
	CC	744124.7768	1640734.913							
	PT	340+91.33	742446.7163	1634974.347						
Tangent	PT	340+91.33	742446.7163	1634974.347						
	PC	340+94.95	742450.1957	1634973.334						
Elmore Curve #16	PC	340+94.95	742450.1957	1634973.334	3811.88	373.08	5°36'27.75"	Left	0.02	35
	PI	342+81.64	742629.4346	1634921.121						
	CC	741384.103	1631313.575							
	PT	344+68.03	742802.7137	1634851.644						
Tangent	PT	344+68.03	742802.7137	1634851.644						
	PC	346+21.64	742945.2854	1634794.479						

Element	Point Type	Station	Northing	Easting	Radius	Length	Delta / Theta	Direction	Maximum Banking	Design Speed
Elmore Curve #17	PC	346+21.64	742945.2854	1634794.479	4900	658.59	7°42'03.05"	Left	NC	35
	PI	349+51.43	743251.386	1634671.746						
	CC	741121.723	1630246.444							
	PT	352+80.22	743538.2795	1634509.102						
Tangent	PT	352+80.22	743538.2795	1634509.102						
	PC	354+63.20	743697.4592	1634418.861						
Elmore Curve #18	PC	354+63.20	743697.4592	1634418.861	2500	105.57	2°25'10.18"	Left	0.024	35
	PI	355+16.00	743743.3854	1634392.825						
	CC	742464.5221	1632244.036							
	PT	355+68.77	743788.1715	1634364.873						
Tangent	PT	355+68.77	743788.1715	1634364.873						
	PC	355+95.08	743810.4867	1634350.946						
Elmore Curve #19	PC	355+95.08	743810.4867	1634350.946	750	256.91	19°37'35.96"	Left	0.058	