

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1					1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				NOTE:
					424					424		CY	COMMON EXCAVATION	203.15				
								550		550		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
					1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								580		580		CY	STRUCTURE EXCAVATION	204.25				
								210		210		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
					960					960		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
					375					375		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
					4.5			0.7		5.2		CWT	EMULSIFIED ASPHALT	404.65				
					1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								1		1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10				
								390		390		LF	STEEL PILING, HP 12 X 74	505.16				
								2		2		EACH	DYNAMIC PILE LOADING TEST	505.45				
					2700					2700		LB	REINFORCING STEEL, LEVEL I	507.11				
					15					15		GAL	WATER REPELLENT, SILANE	514.10				
					56					56		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
					185					185		SY	SHEET MEMBRANE WATERPROOFING, SPRAY APPLIED	520.10				
					56					56		LF	JOINT SEALER, HOT POURED	524.11				
					108					108		LF	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM	525.335				
					1					1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10				
					12					12		EACH	BEARING DEVICE ASSEMBLY, PLAIN ELASTOMERIC PAD	531.16				
					1					1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT NO. 1)	540.10				
					1					1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT NO. 2)	540.10				
					1					1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB NO. 1)	540.10				
					1					1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB NO. 2)	540.10				
							20			20		HR	POWER GRADER RENTAL	608.15				
							20			20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
							20			20		HR	TRUCK RENTAL	608.37				
							20			20		HR	LOADER RENTAL, TYPE I	608.40				
					70					70		MGAL	DUST CONTROL WITH WATER	609.10				
								530		530		CY	STONE FILL, TYPE IV	613.13				
					48					48		LF	PRECAST REINFORCED CONCRETE CURB, TYPE B	616.26				
					625					625		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
					1					1		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51				
					5					5		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
					4					4		EACH	GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING, TL-3	621.747				
					80					80		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
					500					500		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				

PROJECT NAME: PLYMOUTH  
PROJECT NUMBER: ER BRS 0149(5)

FILE NAME: z11c330.xls  
PROJECT LEADER: J. OLUND  
DESIGNED BY: D. MYERS  
QUANTITY SHEET #1

PLOT DATE: 11/05/2012  
DRAWN BY: S. MORGAN  
CHECKED BY: J. OLUND  
SHEET 5 OF 46

REVISION	DESCRIPTION	DATE
ADDENDUM #1	CHANGE REINFORCING STEEL TO LEVEL I	11/05/2012

TYLINTERNATIONAL