

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							520				520		HR	EMPLOYEE TRAINEESHIP	634.10				
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1					1		LS	TRAFFIC CONTROL	641.10				
						1120					1120		LF	4 INCH WHITE LINE	646.20				
						1120					1120		LF	4 INCH YELLOW LINE	646.21				
									395		395		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								100			100		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								50			50		LB	SEED	651.15				
								2			2		LB	SEED, WINTER RYE	651.17				
								246			246		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								135			135		CY	TOPSOIL	651.35				
						230					230		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								160			160		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								820			820		SY	TEMPORARY EROSION MATTING	653.20				
								5			5		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								1			1		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
								1230			1230		LF	PROJECT DEMARCATION FENCE	653.55				
						8.5					8.5		SF	TRAFFIC SIGNS, TYPE A	675.20				
						18					18		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
									35		35		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET) (FPQ)	900.608				
									4		4		EACH	SPECIAL PROVISION (BRIDGE RAILING CONCRETE TRANSITION BARRIER)	900.620				
									186		186		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NEXT D BEAMS) (NEXT 32 D)	900.640				
									1		1		LS	SPECIAL PROVISION (REMOVAL OF TEMPORARY BRIDGE AND APPROACHES)	900.645				
						1					1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
						1					1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650				
						257			60		317		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: PLYMOUTH
PROJECT NUMBER: ER BRS 0149(5)

TYLIN INTERNATIONAL

FILE NAME: z11c330.xls
PROJECT LEADER: J. OLUND
DESIGNED BY: D. MYERS
QUANTITY SHEET #2

PLOT DATE: 09/20/2012
DRAWN BY: S. MORGAN
CHECKED BY: J. OLUND
SHEET 6 OF 46