





## Swift Lift® System

### P61 Swift Lift® Setting Plate, P62 Countersunk Screw

The Dayton Superior P61 Swift Lift Setting Plate and P62 Countersunk Screw combination provide an easy method of placing a Swift Lift Anchor into the surface of a flat panel without obstructing the screeding process. The P61 setting plate is available in two sizes, a 4" unit for use with 4-ton anchors and a 5" unit for use with 8-ton anchors. The P62 screw is available in two sizes to match the setting plates. The 4-ton setup uses a 3/4" long, 5/16" - 18 NC thread screw and the 8-ton setup uses a 3/4" long, 7/16" - 14 NC thread screw.



P61 Swift Lift Setting Plate



P62 Swift Lift Countersunk Screw

#### To Order:

Specify: (1) quantity, (2) name, (3) anchor size.

#### Example:

200, P61 Swift Lift Setting Plates and 200, P62 Countersunk Screws for 4-ton anchors.

### P63 Swift Lift® Stud, P64 Swift Lift Wing Nut

The Dayton Superior P63 Swift Lift Stud and P64 Wing Nut combination is used to set P56 Narrow Recess Plugs. Available in two sizes, 5/16" - 18 NC threads for use with the 1-ton anchor and 7/16" - 14 NC threads for use with 2, 4, 8 and 20-ton P56 anchors.



P63 Swift Lift Stud

Note: The P63 Stud and P64 Wing Nut are not interchangeable with the P56R Recess Plug accessories.



P64 Swift Lift Wing Nut

#### To Order:

Specify: (1) quantity, (2) name, (3) size.


#### Example:

200, P63 Swift Lift Studs and 200 P64 Swift Lift Wing Nuts, 7/16" dia.

### P63PL Swift Lift® Plus Holding Stud, P64PL Swift Lift Plus Wing Nut

The Dayton Superior P63PL Swift Lift Plus Holding Stud is a 3/8" diameter, coil threaded stud with a fixed wing nut and a free-running wing nut used with the P66PL threaded plate to quickly attach the P56PL recess plug to the formwork. The holding stud is inserted through the form and threaded into the threaded plate. Complete the anchor installation by screwing the free-running wing nut tightly against the form.


The P64PL Wing Nut has 3/8" diameter coil thread and is available as a replacement nut for the P63PL Holding Stud.



P63PL Swift Lift Plus Holding Stud



P64PL Swift Lift Plus Wing Nut



Tie Swift Lift Anchor to reinforcing steel to ensure anchor support during concrete placement.

#### To Order:

Specify: (1) quantity, (2) name.

#### Example:

200, P63PL Swift Lift Plus Holding Studs.