

SUMMARY OF LONG LINE QUANTITIES BY ROUTE

ROUTE	TOWN	MM	TO	MM	4' ' WHITE LINE	MATERIAL	4' ' YELLOW LINE	MATERIAL	REMARKS
US 2	BERLIN	0.00	-	1.39	14,680	PAINT	14,290	PAINT	
US 2	BARRE TOWN	0.00	-	0.09	910	PAINT	570	PAINT	
US 2	EAST MONTPELIER	0.00	-	4.82	50,900	PAINT	44,730	PAINT	
US 2	PLAINFIELD	0.00	-	1.49	15,788	PAINT	12,618	PAINT	
US 2	MARSHFIELD	0.00	-	8.21	86,785	PAINT	84,540	PAINT	
US 2	CABOT	0.00	-	1.50	-	-	-	-	2011 PROJECT NO WORK
US 2	CABOT	1.50	-	6.23	51,760	PAINT	48,260	PAINT	
US 2	DANVILLE	0.00	-	4.05	43,020	PAINT	39,090	PAINT	
US 2	DANVILLE	4.05	-	4.75	-	-	-	-	2011 PROJECT NO WORK
US 2	DANVILLE	4.75	-	6.50	18,480	PAINT	18,480	PAINT	
US 2	ST JOHNSBURY	4.70	-	8.64	41,760	PAINT	40,660	PAINT	
US 2	KIRBY	0.00	-	0.97	10,190	PAINT	10,190	PAINT	
US 2	CONCORD	0.00	-	10.78	112,930	PAINT	94,320	PAINT	
US 2	LUNENBURG	0.00	-	9.03	94,616	PAINT	80,696	PAINT	
US 2	GUILDHALL	0.00	-	1.16	12,220	PAINT	10,450	PAINT	
	TOTAL US 2				556,400		498,143		

NOTE: MATERIAL USED FOR PAVEMENT MARKING
 PAINT = WATERBORNE TRAFFIC PAINT
 POLYUREA

ROUTE QUANTITIES
SHEET 3

PROJECT NAME: **STATEWIDE**
 PROJECT NO.: **NHG MARK (205)**
 DESIGN FILE NAME: IIB010.dgn
 PROJECT MANAGER: A GAMBLE
 IPARM FILE NAME: IIB010r03.i

PLOT DATE: 31-MAY-2012 13:11
 DRAWN BY: KAS
 SHEET: **5R** OF 26