SUMMARY OF HAND WORK BY ROUTE

ROUTE	TOWN	MM	STENCIL	4" WHITE LINE	8" YELLOW LINE	8" WHITE LINE	STOP BAR	LETTER & SYM.	CROSS WALK	4" YELLOW LINE	RR XING	REMARKS
US 7	SO. BURLINGTON	1.24	ARROW(4) ONLY(2)	351 FEET	-	-	72 FEET	12	-	-	-	JCT BALDWIN AVE
US 7	SO. BURLINGTON	1.29	ARROW(2)	-	-	-	-	2	-	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.32	ARROW(2)	-	-	-	-	2	-	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.34	ARROW(2)	-	-	-	-	2	-	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.37	ARROW(2)	-	-	-	-	2	-	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.44	ARROW(6) ONLY(3)	390 FEET	-	-	84 FEET	18	-	-	-	JCT BURGER KING
US 7	SO. BURLINGTON	1.53	ARROW(6) ONLY(3)	409 FEET	-	-	84 FEET	18	-	-	-	JCT K-MART
US 7	SO. BURLINGTON	1.58	ARROW(2)	-	-	-	-	2	-	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.61	ARROW(2)	-	-	-	-	2	-	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.63	8'' WHITE LINE	-	-	328 FEET	-	-	-	-	-	DO NOT BLOCK INTERSECTION
US 7	SO. BURLINGTON	1.64	ARROW(2)	-	-	-	-	2	-	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.65	ARROW(1)	-	228 FEET	-	47 FEET	1	-	135 FEET	-	
US 7	SO. BURLINGTON	1.67		-	-	-	-	-	67 FEET	-	-	
US 7	SO. BURLINGTON	1.69	ARROW(2)	-	-	-	-	2	-	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.70	DBL ARROW(1)	-	-	180 FEET	-	2	-	-	-	
US 7	SO. BURLINGTON	1.72	DBL ARROW(1)	284 FEET	77 FEET	-	36 FEET	2	-	71 FEET	-	
										2515 FEET		
	TOTAL US 7			11,290 FEET	10,457 FEET	2,070 FEET	1,695 FEET		1,325 FEET		6	
US 7	SO. BURLINGTON	0.95	ARROW(2)					2				
US 7	SO. BURLINGTON	0.98	ARROW(2) ONLY(1)	126 FEET				6				
US 7	SHELBURNE	3.00	ARROW(3)					3				
								861				

NOTE: ALL HAND WORK IS WATERBORNE TRAFFIC PAINT

HAND WORK

QUANTITIES SHEET 6

PROJECT NAME: **STATEWIDE**
PROJECT NO.: **NHG MARK (205)**
DESIGN FILE NAME: IIb010.dgn
PROJECT MANAGER: A GAMBLE
IPARM FILE NAME: IIb010hw6.i
PLOT DATE: 31-MAY-2012 13:II
DRAWN BY: KAS
SHEET: 15R OF 26