QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

TRAINING	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						BEGIN ITEMS COMMON TO ALL ALTERNATES		
		49 000		49 000	LF	SHOULDER BERM REMOVAL	203.40	EST.
		1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
		26 500		26 500	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	115
		311000		311000	LF	MILLED RUMBLE STRIPS	213.10	700
		250		250	TON	AGGREGATE SHOULDERS	402.12	42
		2 300		2 300	TON	AGGREGATE SHOULDERS, RAP	402.13	-
		1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
		34 500		34 500	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	EST
	650			650	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	3
	100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
		400		400	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
		3 000		3 000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
		4 000		4 000	HR	FLAGGERS	630.15	EST
			1	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
			1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			3 000	3 000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
520				520	HR	EMPLOYEE TRAINEESHIP	634.10	-
		1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
		1		1	LS	TRAFFIC CONTROL	641.10	-
		2		2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
		4 600		4 600	LF	4 INCH WHITE LINE	646.20	92
		3 000		3 000	LF	4 INCH YELLOW LINE	646.21	140
		523 000		523 000	LF	6 INCH WHITE LINE	646.214	536
		382 000		382 000	LF	6 INCH YELLOW LINE	646.215	689
		1000		1000	LF	8 INCH WHITE LINE	646.22	EST
		12 200		12 200	LF	12 INCH WHITE LINE	646.24	30
		1900		1900	LF	12 INCH YELLOW LINE	646.25	80
		550		550	LF	24 INCH STOP BAR	646.26	14
		230		230	EA	LETTER OR SYMBOL	646.30	5
		2 500		2 500	LF	TEMPORARY 4 INCH WHITE LINE	646.600	246
		1500		1500	LF	TEMPORARY 4 INCH YELLOW LINE	646.610	70
		259 000		259 000	LF	TEMPORARY 6 INCH WHITE LINE	646.620	228
		189 000		189 000	LF	TEMPORARY 6 INCH YELLOW LINE	646.630	987
		1000		1000	LF	TEMPORARY 8 INCH WHITE LINE	646.640	EST
		6 100		6 100	LF	TEMPORARY 12 INCH WHITE LINE	646.660	15
		950		950	LF	TEMPORARY 12 INCH YELLOW LINE	646.670	40
		300		300	LF	TEMPORARY 24 INCH STOP BAR	646.680	32

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BENNINGTON-MANCHESTER
PROJECT NUMBER: NH SURF (29)

FILE NAME: 11b026\11b026.dgn
PROJECT LEADER: FOWLER
DESIGNED BY: PVT. MGT.
IPARM FILE NAME: 11b026-8.i

PLOT DATE: 22-AUG-2013 14:3
DRAWN BY: PVT.MGT.
CHECKED BY: PAVT MGMT
SHEET 8 OF 63